

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 946	05-00074-00-RS	ALEXANDER	15	3
PROJECT NO. RS-946 (106)			CONTRACT NO. 99287	

**RESURFACING SCHEDULE - SOUTHBOUND (RIGHT) LANE**

Location Station to Station	Length	Bituminous Materials (Prime Coat)	Leveling Binder Mach. Method	Hot-Mix Asphalt Surface Cse.
	Feet	Gallons	Tons	Tons
<b>SOUTHBOUND (RIGHT) LANE</b>				
1+11 to 6+83	572.00	72.0	79.7	50.6
6+83 to 15+30	847.00	106.6	114.3	75.0
15+30 to 21+54	624.00	78.6	61.4	55.2
21+54 to 29+02	748.00	94.2	68.7	66.2
29+02 to 35+95	693.00	87.2	62.0	61.3
35+95 to 44+48	853.00	107.4	63.0	75.4
44+48 to 65+08	2060.00	259.3	182.2	182.3
65+08 to 73+01	793.00	101.6	55.5	72.5
73+01 to 76+08	307.00	39.7	18.9	28.7
76+08 to 82+47	639.00	80.5	51.7	56.5
82+47 to 90+05	758.00	95.4	63.9	67.1
90+05 to 100+52	1047.00	131.8	102.8	92.6
100+52 to 107+28	676.00	85.1	65.2	59.8
107+28 to 109+23	195.00	24.6	14.9	17.3
109+23 to 115+79	656.00	82.5	51.9	58.0
115+79 to 130+81	1502.00	189.1	311.0	132.9
130+81 to 138+53	772.00	97.2	115.7	68.4
138+53 to 154+82	1629.00	205.1	162.8	144.1
154+82 to 161+18	636.00	80.1	52.1	56.3
161+18 to 202+36	4118.00	518.4	312.7	364.3
202+36 to 210+82	846.00	106.5	61.0	74.9
210+82 to 214+92	410.00	51.6	27.5	36.3
214+92 to 219+63	471.00	59.3	30.7	41.6
219+63 to 226+92	729.00	91.7	51.4	64.5
226+92 to 232+71	579.00	72.9	47.0	51.3
232+71 to 238+00	491.00	61.8	30.8	43.4
<b>Totals for SouthBound (Right) Lane</b>		<b>2980.2</b>	<b>2258.8</b>	<b>2096.5</b>

**RESURFACING SCHEDULE - NORTHBOUND (LEFT) LANE**

Location Station to Station	Length	Bituminous Materials (Prime Coat)	Leveling Binder Mach. Method	Hot-Mix Asphalt Surface Cse.
	Feet	Gallons	Tons	Tons
<b>NORTHBOUND (LEFT) LANE</b>				
1+11 to 6+83	572.00	72.0	86.2	50.6
6+83 to 15+30	847.00	106.6	88.2	75.0
15+30 to 21+54	624.00	78.6	52.1	55.2
21+54 to 29+02	748.00	94.2	65.2	66.2
29+02 to 35+95	693.00	87.2	96.2	61.3
35+95 to 44+48	853.00	107.4	63.4	75.4
44+48 to 65+08	2060.00	259.3	166.2	182.3
65+08 to 73+01	793.00	101.6	61.0	72.5
73+01 to 76+08	307.00	39.7	21.5	28.7
76+08 to 82+47	639.00	80.5	73.6	56.5
82+47 to 90+05	758.00	95.4	79.9	67.1
90+05 to 100+52	1047.00	131.8	147.8	92.6
100+52 to 107+28	676.00	85.1	74.4	59.8
107+28 to 109+23	195.00	24.6	18.5	17.3
109+23 to 115+79	656.00	82.5	52.0	58.0
115+79 to 130+81	1502.00	189.1	201.3	132.9
130+81 to 138+53	772.00	97.2	74.0	68.4
138+53 to 154+82	1629.00	205.1	145.4	144.1
154+82 to 161+18	636.00	80.1	67.7	56.3
161+18 to 202+36	4118.00	518.4	389.0	364.3
202+36 to 210+82	846.00	106.5	66.5	74.9
210+82 to 214+92	410.00	51.6	39.9	36.3
214+92 to 219+63	471.00	59.3	46.5	41.6
219+63 to 226+92	729.00	91.7	67.8	64.5
226+92 to 232+71	579.00	72.9	75.8	51.3
232+71 to 238+00	491.00	61.8	55.5	43.4
<b>Totals for NorthBound (Left) Lane</b>		<b>2980.2</b>	<b>2381.6</b>	<b>2096.5</b>

NOTE: Quantities shown do not include materials for entrances, side roads, and mailbox turnouts.

RESURFACING SCHEDULE  
 FAS ROUTE 946  
 SECTION 05-00074-00-RS  
 PROJECT NO. RS-946 (106)  
 ALEXANDER COUNTY