

07A0J 07C0J 07P05
 80% STATE 100% STATE 100% STATE

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				0003	0003 20% LOCAL 80% STATE	0003 100% LOCAL	0010 SN 049-0533	0010 SN 049-0534	0021 SAFETY
50500305	ERECTING STRUCTURAL STEEL	L SUM	1				0.45	0.55	
50500505	STUD SHEAR CONNECTORS	EACH	5,148				2,376	2,772	
50800105	REINFORCEMENT BARS	POUND	390	390					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	369,580				182,490	187,090	
50800515	BAR SPLICERS	EACH	344				172	172	
50901735	BRIDGE FENCE RAILING (SIDEWALK)	FOOT	393			** 66(L)	157	170	
50901750	PARAPET RAILING	FOOT	387			*** 90(L)	143	154	
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	4,827				2,489	2,338	
51202305	DRIVING PILES	FOOT	4,827				2,489	2,338	
51203200	TEST PILE METAL SHELLS	EACH	4				2	2	
51204650	PILE SHOES	EACH	88				44	44	
51500100	NAME PLATES	EACH	2				1	1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	348				174	174	
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	22				11	11	
52100520	ANCHOR BOLTS, 1"	EACH	88				44	44	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	12	12					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4	4					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1					
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	1	1					
54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48"	EACH	2	2					
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	74	74					
542A2761	PIPE CULVERTS, CLASS A, TYPE 4 36"	FOOT	25	25					
542A4663	PIPE CULVERTS, CLASS A, TYPE 7 48"	FOOT	88	88					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	785	785					
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	81	81					
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	412	412					
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	43	43					
550A0940	STORM SEWERS, CLASS A, TYPE 4 12"	FOOT	48	48					
55100200	STORM SEWER REMOVAL 6"	FOOT	28	28					
55100500	STORM SEWER REMOVAL 12"	FOOT	305	305					

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				0003	0003 20% LOCAL 80% STATE	0003 100% LOCAL	0010 SN 049-0533	0010 SN 049-0534	0021 SAFETY
55101200	STORM SEWER REMOVAL 24"	FOOT	25	25					
58700300	CONCRETE SEALER	SQ FT	3,175				1,528	1,647	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	24	24					
60107600	PIPE UNDERDRAINS 4"	FOOT	8,709	8,709					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	705	705					
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3					
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	27	27					
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4					
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	3	3					
60500040	REMOVING MANHOLES	EACH	1	1					
60500050	REMOVING CATCH BASINS	EACH	1	1					
60500060	REMOVING INLETS	EACH	6	6					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6	6					
60600605	CONCRETE CURB, TYPE B	FOOT	196	60	136				
60602800	CONCRETE GUTTER, TYPE B	FOOT	630	630					
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	54	54					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,495	1,495					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3,159	3,159					
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	1,740	1,740					
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1564.5	1564.5					
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4					
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1					
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2					
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	5	5					
63200310	GUARDRAIL REMOVAL	FOOT	1,524	1,524					
63300705	RUB RAIL	FOOT	93	93					
63500105	DELINEATORS	EACH	98	98					

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com

• SPECIALTY ITEMS
 NOTES:
 1. COLUMN FOR "0003 20% LOCAL 80% STATE" THE LOCAL AGENCY IS LAKE COUNTY HIGHWAY DEPARTMENT
 2. COLUMN FOR "0003 100% LOCAL" THE LOCAL AGENCY IS VILLAGE OF WADSWORTH

3. (W) 100% VILLAGE OF WADSWORTH
 4. (L) 100% LAKE COUNTY

** 32 FT. SN 049-0533, 34 FT. SN 049-0534
 *** 43 FT. SN 049-0533, 47 FT. SN 049-0534

FILE NAME: #FILES#	USER NAME: default	DESIGNED: RGR	REVISED:	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE. 94	SECTION 49-(HB & HB-1)R	COUNTY LAKE	TOTAL SHEETS 225	SHEET NO. 4
PLOT SCALE: #SCALE#	PLT DATE: 2/18/2012	CHECKED: RGR	REVISED:	SCALE: NA	SHEET NO. 2 OF 4 SHEETS	STA. NA	TO STA. NA	CONTRACT NO. 60L76		
ILLINOIS FED. AID PROJECT										

S:\118195-CADD\60L76-Sheet\A\DIGI\76-shr-1-10-12.dgn