SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY (URBAN)	0003 100% STATE	0003 20% LOCAL 80% STATE (80% STATE 20% LAKE CO. H.D.)	0003 100% LOCAL (WADSWORTH)	0010 SN 049-0533 (100% STATE)	0010 SN 049-0534	0021 SAFETY (100% STATE)
66400105	CHAIN LINK FENCE, 4'	FOOT	2769	2769					
66406400	CHAIN LINK GATES, 4'X24' DOUBLE	EACH	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	13	13					
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	13	13					
67100100	MOBILIZATION	L SUM	1	1					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	56	56					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	28,800	28,800					
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	671	671					
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	141	141					
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ FT	7,225	7,225					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4637.5	4637.5					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	6075	6075					
72000100	SIGN PANEL - TYPE 1	SQ FT	147	147					
72000200	SIGN PANEL - TYPE 2	SQ FT	34	34					
72000300	SIGN PANEL - TYPE 3	SQ FT	258	258					
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	16	16					
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	16	16					
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	27	27					
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	203	203					
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2,210	2,210					
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	18	18					
73000100	WOOD SIGN SUPPORT	FOOT	328	328					
73400100	CONCRETE FOUNDATIONS	CU YD	5	5					
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	4	4					
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4	4					
78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	15,532	13,048		2,484 (W)			
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	1298	1298					
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	946	946					
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	35001	35001					
78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	11766	11766					
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	3571	3571					
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1234	1234					
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	2814	2814					
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	538	538					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	89	89					
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8					
78200300	PRISMATIC CURB REFLECTOR	EACH	22	22					
78200410	GUARDRAIL MARKERS, TYPE A	EACH	13	13					
78200530	BARRIER WALL MARKERS, TYPE C	EACH	824	824					
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,059	2,059					
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1						1
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1						1
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2	2					
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	68						68
* 81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	80						80
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	617						617
* 81300610	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 14" X 12" X 6"	EACH	4						4
* 81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	502						502
* 81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	96						96
* 81702410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 4	FOOT	695						695
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	4233						4233
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	23						23
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	21						21
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	2						2
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	8						8
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	8						8
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
* 86000105	MASTER CONTROLLER (SPECIAL)	EACH	1	1					

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

* SPECIALTY ITEMS

NOTES:
1. COLUMN FOR "0003 20% LOCAL 80% STATE" THE LOCAL AGENCY IS LAKE COUNTY HIGHWAY DEPARTMENT
2. COLUMN FOR "0003 100% LOCAL" THE LOCAL AGENCY IS VILLAGE OF WADSWORTH

3. (W) 100% VILLAGE OF WADSWORTH
4. (L) 100% LAKE COUNTY

Rev.

FILE NAME = $FILES$	USER NAME = default	DESIGNED - RGR	REVISED -
		DRAWN - RGR	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - RGR	REVISED -
	PLOT DATE = 2/10/2012	DATE - 01/25/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA | SHEET NO. 3 OF 4 SHEETS | STA. NA | TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1(HB & HB-1)R	LAKE	225	5
		CONTRACT NO. 60L76		
	ILLINOIS FED. AID PROJECT			

S:\11181\DS\CADD\60L76 Russell Rev\60L76 Sheets\10160L76-sht-sod.dgn