

SIGNING SCHEDULE			EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL - TYPE 3	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL ASSEMBLY - TYPE B	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	CONCRETE FOUNDATION	REINFORCEMENT BARS	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATION - GROUND MOUNT			
SIGN NUMBER	STATION	PANEL LEGEND / DESCRIPTION	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	(SQ FT)	(SQ FT)	(EACH)	(EACH)	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(POUND)	(CU YD)	(POUND)	(EACH)	(EACH)			
WB-1	0+62	R1-1	3	3	3	3				1	9			16.5									
		R1-I100	2.5	1.5	2.5	1.5					3.75												
WB-2	0+72	RUSSELL RD			3	1								BY LCDOT									
		OLD SKOKIE RD			4	1																	
WB-3	0+88	M4-5	2	1	2	1																	
		M4-15	2	1	2	1																	
		M3-2	2	1	2	1																	
		M1-1	2	2	2	2																	
		M6-1	1.75	1.25	1.75	1.25				1		BY LCDOT			BY LCDOT								
		M3-3	2	1	2	1																	
		M1-4	2	2	2	2																	
		M6-1	1.75	1.25	1.75	1.25																	
		RENAISSANCE FAIR	4	2	4	2																	
WB-4	4+16	M4-5	2	1	2	1																	
		M4-15	2	1	2	1																	
		M3-2	2	1	2	1																	
		M1-1	2	2	2	2																	
		M5-1	1.75	1.25	1.75	1.25				1		BY LCDOT			BY LCDOT								
		M3-3	2	1	2	1																	
		M1-4	2	2	2	2																	
		M5-1	1.75	1.25	1.75	1.25																	
		R7-1	1	1.5																			
WB-5	6+97	W3-1	2.5	2.5	2.5	2.5			1		BY LCDOT			BY LCDOT									
		OLD SKOKIE RD	2	1	2	0.67																	
WB-6	8+20	R5-1			2.5	2.5					6.25		17.4										
WB-7	8+24	R1-1	2.5	2.5	2.5	2.5				1	6.25			16.6									
		R5-1	2.5	2.5																			
WB-8	8+77	R1-1	2.5	2.5	2.5	2.5			1														
		R6-1 LT			3	1					BY LCDOT				BY LCDOT								
WB-9	9+32	R5-1			2.5	2.5																	
		R6-1 LT			3	1					BY LCDOT			BY LCDOT									
WB-10	9+39	R3-2	2	2																			
		R3-1	2	2					1														
WB-11	11+40	R3-1			2	2								BY LCDOT									
WB-12	15+59	R2-1	2	2.5	2	2.5			1		BY LCDOT			BY LCDOT									
WB-13	16+34	M4-5	2	1	2	1																	
		M4-15	2	1	2	1																	
		M3-2	2	1	2	1																	
		M1-1	2	2	2	2																	
		M6-3	1.75	1.25	1.75	1.25				1		BY LCDOT			BY LCDOT								
		M3-3	2	1	2	1																	
		M1-4	2	2	2	2																	
WB-14	18+53	M6-3	1.75	1.25	1.75	1.25																	
WB-15	18+97	R3-2	3	3			9																
WB-16	19+99	I-94 WEST/US-41 NORTH/MILWAUKEE, ARROW	14.5	7	15	7.5		101.5				112.5			1097	2.54	196	2		2			
WB-17	21+92	W1-7	4	2	4	2			1		BY LCDOT			BY LCDOT									
		M2-1	1.75	1.25	1.75	1.25																	
WB-18	23+21	M1-1	2	2	2	2				1	BY LCDOT			BY LCDOT									
		M1-4	2	2	2	2																	
WB-19	28+78	M4-6	2	1																			
		M1-6	2	2	2	2			1		BY LCDOT			BY LCDOT									
		RUSSELL RD	2.5	0.67	2.5	0.67																	
		M3-4			2	1																	
		R2-1			2	2.5								BY LCDOT									

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



FILE NAME = #FILES#	USER NAME = default	DESIGNED - MAB	REVISED -
		DRAWN - MAB	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 01/25/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING SCHEDULE

SCALE: SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1(HB & HB-1)R	LAKE	225	75
CONTRACT NO. 60L76			ILLINOIS FED. AID PROJECT	

S:\1101\95\CADD\60L76_Russell_Rdwy\60L76_Sheets\0160L76_sht-rmkSCH.dgn