ROUTE: Edens Expressway (NB to EB Willow Rd) - Jointed Pavement | PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
		EB to SB	Ramp	16	6	96	11
				16	12	192	21
				16	6	96	11
				16	22	352	39
				16	56	896	100
		TOTALS:			102 FT		182 SY

ROUTE: Edens Expressway (SB Wilson Ave Entrance Ramp) - Jointed Pavement | PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
		SB	Ramp	16	6	96	11
				24	6	144	16
				30	6	180	20
				16	15	240	27
				16	30	480	53
				16	45	720	80
		TOTALS:			108 FT		207 SY

ROUTE: Edens Expressway (NB Tower Entrance Ramp) - Jointed Pavement | PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
		NB	Radius	17	6	102	11
			Radius	31	8	248	28
			Radius	4	60	240	27
			Ramp	16	6	96	11
			Ramp	16	6	96	11
			Ramp	16	6	96	11
			Ramp	16	6	96	11
			Ramp	16	6	96	11
			Ramp	16	12	192	21
			Ramp	16	12	192	21
			Ramp	16	14	224	25
			Ramp	16	12	192	21
			Ramp	16	6	96	11
			Ramp	16	6	96	11
			Ramp	16	12	192	21
			Ramp	16	6	96	11
			Ramp	16	6	96	11
			Ramp	16	6	96	11
			Ramp	16	6	96	11
		TOTALS:			208 FT		304 SY

ROUTE: Edens Expressway (Lake-Cook Rd to Chantilly) - CRC Pavement | PATCHING = CLASS A

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Lake - Cook Road	Chantilly Drive	NB	1	12	6	72	8
		NB	3	12	6	72	8
		NB	2	12	6	72	8
		NB	1	12	6	72	8
		NB	2	12	6	72	8
		NB	3	12	20	240	27
		NB	2	12	6	72	8
		NB	1	12	75	900	100
		NB	1	12	12	144	16
		NB	Taper	16	8	128	14
		NB	Taper	16	8	128	14
		SB	1	12	8	96	11
		SB	1	12	100	1200	133
		SB	1	12	50	600	67
		SB	1	12	50	600	67
		SB	1	12	6	72	8
		SB	1	12	100	1200	133
		SB	2	12	6	72	8
		SB	3	12	6	72	8
		SB	2	12	12	144	16
		SB	1	12	6	72	8
		SB	2	12	6	72	8
		SB	3	12	6	72	8
		TOTALS:			515 FT		694 SY