

SUMMARY OF QUANTITIES								
CODE NUMBER	DESIGNATION	UNIT	TOTAL QUANTITY	90% FEDERAL		CONSTRUCTION CODE TYPE: 0021		
				URBAN	5% STATE	5% STATE	10% STATE	5% STATE
					5% MCHENRY COUNTY	5% WOODSTOCK		5% WOODSTOCK
				US RTE. 14 @ KISHWAUKEE VALLEY ROAD	US RTE. 14 @ DEAN STREET	US RTE. 14 @ ILL. RTE. 47	US RTE. 14 @ LAKE AVENUE	
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7		4	-	3	
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	1		-	-	1	
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	9		2	4	1	
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	10		2	4	2	
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3		-	-	1	
88030230	SIGNAL HEAD, LED, 2-FACE, 1-3-SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1		-	-	1	
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3-SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2		-	-	2	
88500100	INDUCTIVE LOOP DETECTOR	EACH	12		8	4	-	
88600100	DETECTOR LOOP, TYPE I	FOOT	122		54	68	-	
88700200	LIGHT DETECTOR	EACH	2		2	-	-	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1	-	-	
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	3		-	1	1	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4		1	1	1	
X8620200	UNINTERRUPTIBLE POWER SUPPLY, SPECIAL	EACH	4		1	1	1	
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	386		386	-	-	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4		25.7	-	25.7	
X8820010	TRAFFIC SIGNAL BACKPLATE, SPECIAL	EACH	40		6	8	12	

100% COST TO CITY OF WOODSTOCK

FILE NAME #	USER NAME # USER#	DESIGNED - PKG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - EA, MG	REVISED -					305	2011-020-TS	MCHENRY	20	3A
	PLOT SCALE # SCALE#	CHECKED - PKG	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. G0P15				
	PLOT DATE # DATE#	DATE - 06/01/2011	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							