

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				DuPAGE CO 90% FED 10% STATE URBAN 0021 QUANTITY	DuPAGE CO 100% STATE URBAN 0021 QUANTITY	COOK CO 90% FED 10% STATE URBAN 0021 QUANTITY	COOK CO 100% STATE URBAN 0021 QUANTITY
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	1	-	6	-
50800105	REINFORCEMENT BARS	POUNDS	1960	1960			
67100100	MOBILIZATION	L SUM	1	0.1	-	0.9	-
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.1	-	0.9	-
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	49	-	-	49	-
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	839	132	-	707	-
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	511	98	-	413	-
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	20,921	1,533	-	19,388	-
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	16	-	-	16	-
72600100	MILE POST MARKER ASSEMBLY	EACH	21	2		19	
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	9595	-	-	9595	1
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1026	36	-	990	-
73000100	WOOD SIGN SUPPORT	FOOT	7812	540	-	7,272	-
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	179.5	-	-	179.5	-
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	18.5	-	-	18.5	-
73400100	CONCRETE FOUNDATIONS	CU YD	20	-	-	20	-
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	58.4	-	-	58.4	-
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	3	-	-	3	-
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	16	-	-	16	-
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	16	-	-	16	-
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	5	-	-	5	-
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	224	17	-	207	-
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.1	-	0.9	-
X7200105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	3073	278	60	2283	452
X7200205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	2353	206	-	2147	23
X7200305	SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	24,313	635	1085	3178	19,415
X7240200	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL)	EACH	233	25	-	208	-
X7360300	REMOVE OVERHEAD SIGN STRUCTURE - WALKWAY	FOOT	1,087	75	-	1,012	-

* INDICATES SPECIALTY ITEM

Rev. 4-12-12

Rev.

*F.A.I. 290 (INTERSTATE 290)
*F.A.U. 342 (IL ROUTE 53)

COPYRIGHT 2009 BY BAXTER & WOODMAN, INC. ALL RIGHTS RESERVED. PROJECT NO. 2011-024-SG. SHEET NO. 132 OF 132. DATE: 2/6/2012. DRAWN BY: UKB. CHECKED BY: RWL. DESIGNED BY: DJS. REVISIONS: 1. REVISED: 2/6/2012. 2. REVISED: 4/12/2012.



USER NAME : 231ukb	DESIGNED - DJS	REVISED -
DRAWN - UKB	CHECKED - RWL	DATE - 12-13-11

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2011-024-SG	DuPAGE/COOK	132	3
CONTRACT NO. 60P24			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	