

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				DuPAGE CO 90% FED 10% STATE URBAN 0021 QUANTITY	DuPAGE CO 100% STATE URBAN 0021 QUANTITY	COOK CO 90% FED 10% STATE URBAN 0021 QUANTITY	COOK CO 100% STATE URBAN 0021 QUANTITY
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	1	-	6	-
50800105	REINFORCEMENT BARS	POUNDS	1960	1	-	1960	-
67100100	MOBILIZATION	L SUM	1	0.1	-	0.9	-
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.1	-	0.9	-
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	49	-	-	49	-
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	839	132	-	707	-
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	511	98	-	413	-
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	20,921	1,533	-	19,388	-
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	16	-	-	16	-
72600100	MILE POST MARKER ASSEMBLY	EACH	21	2	-	19	-
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	9595	-	-	9595	1
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1026	36	-	990	-
73000100	WOOD SIGN SUPPORT	FOOT	7812	540	-	7,272	-
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	179.5	-	-	179.5	-
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	18.5	-	-	18.5	-
73400100	CONCRETE FOUNDATIONS	CU YD	20	-	-	20	-
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	58.4	-	-	58.4	-
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	3	-	-	3	-
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	16	-	-	16	-
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	16	-	-	16	-
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	5	-	-	5	-
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	224	17	-	207	-
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.1	-	0.9	-
X7200105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	3073	278	60	2283	452
X7200205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	2353	206	-	2147	23
X7200305	SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	24,313	635	1085	3178	19,415
X7240200	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL)	EACH	233	25	-	208	-
X7360300	REMOVE OVERHEAD SIGN STRUCTURE - WALKWAY	FOOT	1,087	75	-	1,012	-

* INDICATES SPECIALTY ITEM

Rev. 4-12-12

Rev.

*F.A.I. 290 (INTERSTATE 290)
*F.A.U. 342 (IL ROUTE 53)

2009, BY BAXTER & WOODMAN, INC.
 ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM.
 LICENSE NO. 184-00021 - EXPRESSES 4/30/2013
 PROJECT NO. 2011-024-5G
 SHEET NO. 132 OF 132
 CONTRACT NO. 60P24



USER NAME : 231ukb	DESIGNED - DJS	REVISED -
DRAWN - UKB	CHECKED - RWL	DATE - 12-13-11
PLOT SCALE : 50.0000' / 1" =		
PLOT DATE : 2/6/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.
--------	---------------------	--------------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2011-024-5G	DuPAGE/COOK	132	3
CONTRACT NO. 60P24		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		

SIGNING SCHEDULE

SIGN NAME	STATION	SIGN DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL TYPE 1	REMOVE SIGN PANEL TYPE 2	REMOVE SIGN PANEL TYPE 3	REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B (SPECIAL)	RELOCATE SIGN PANEL TYPE 1	SIGN PANEL TYPE 1 (SPECIAL)	SIGN PANEL TYPE 2 (SPECIAL)	SIGN PANEL TYPE 3 (SPECIAL)	WOOD SIGN SUPPORT (FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	REMOVAL OF LIGHTING UNIT, NO SALVAGE (EACH)	REMOVE OVERHEAD SIGN STRUCTURE - WALKWAY (FOOT)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	(SQ. FT)	(SQ. FT)	(SQ. FT)	(EACH)	(EACH)	(SQ. FT)	(SQ. FT)	(SQ. FT)	(SQ. FT)	(SQ. FT)	(SQ. FT)	(SQ. FT)	(SQ. FT)
PAL-WP-8109A	37+15	M3-3 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
PAL-WP-8109B	37+15	M1-1100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
PAL-WP-8109C	37+15	M5-2R -- WHITE BACKGROUND	2.5	1.8	2.5	1.8							4.4						
PAL-WP-8110	39+12	W13-7 -- 25 MPH	4.0	7.0	4.0	7.0					1				28.0	18			
PAL-WP-8111A	39+25	M3-1 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
PAL-WP-8111B	39+25	M1-1100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
PAL-WP-8111C	39+25	M6-2R -- WHITE BACKGROUND	2.5	1.8	2.5	1.8							4.4						
PAL-WP-8112	40+10	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
PAL-WP-8113	42+00	W4-1R -- MERGE	4.0	4.0	4.0	4.0					1			16.0		18			
PAL-WP-8114	45+20	W13-3 -- 25 MPH	4.0	5.0	4.0	5.0					1			20.0		18			
PAL-WP-8115A	45+37	M3-3 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5							4.5						
PAL-WP-8115B	45+37	M1-1100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
PAL-WP-8115C	45+37	M6-3 -- WHITE BACKGROUND	2.5	1.8	2.5	1.8							4.4						
PAL-WP-8115D	45+37	M3-1 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5							4.5						
PAL-WP-8115E	45+37	M1-1100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
PAL-WP-8115F	45+37	M6-2R -- WHITE BACKGROUND	2.5	1.8	2.5	1.8							4.4						
PAL-WP-8116A	51+82	M3-3 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5					1		4.5			18			
PAL-WP-8116B	51+82	M1-1100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
PAL-WP-8116C	51+82	M6-3 -- WHITE BACKGROUND	2.5	1.8	2.5	1.8							4.4						
PAL-WP-8116D	51+82	M3-1 -- WHITE BACKGROUND	3.0	1.5	3.0	1.5							4.5						
PAL-WP-8116E	51+82	M1-1100 -- IL 53	3.0	3.0	3.0	3.0							9.0						
PAL-WP-8116F	51+82	M5-2R -- WHITE BACKGROUND	2.5	1.8	2.5	1.8							4.4						
PAL-WP-8117A	54+30	M2-1 -- WHITE BACKGROUND	-	-	2.5	1.8							4.4			18			
PAL-WP-8117B	54+30	M1-1100 -- IL 53	-	-	3.0	3.0							9.0						
TOTALS							839	511	20,921	49	233	16	3,073	2,353	24,313	7,812	1,026	224	1,087

GROUND MOUNT SCHEDULE

SIGN NAME	STATION	SIGN DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		NUMBER OF POSTS	POST TYPE	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY (POUNDS)	CONCRETE FOUNDATIONS (CU YD)	REINFORCEMENT BARS (POUND)	REMOVE GROUND MOUNTED SIGN SUPPORT (EACH)	REMOVE CONCRETE FOUNDATION - GROUND MOUNT (EACH)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)							
NEB-GM-1084	318+09	90 EAST/CHICAGO, 1/4 MILE	15.5	14.0	15.5	14.0	2	W14X38	2242	4.2	244	2	2
SWB-GM-1126	410+74	EXPRESS LANES EXIT TO HIGGINS RD PROHIBITED	13.5	8.5	-	-	-	-	-	-	-	2	2
NEB-WP-1131	430+86	ARLINGTON PARK RACECOURSE NEXT RIGHT	9.5	4.5	9.5	4.5	-	-	-	-	2	2	
SWB-WP-1154	480+02	ARLINGTON PARK RACECOURSE SECOND RIGHT	9.5	4.5	9.5	4.5	-	-	-	-	2	2	
NEB-GM-1160	501+00	PARK & RIDE NEXT RIGHT	-	-	10.5	7.0	2	W6X15	525	1.4	156	-	-
SWB-GM-1169	535+71	PARK & RIDE NEXT RIGHT	10.5	7.0	10.5	7.0	2	W6X15	525	1.4	156	-	-
BIE-GM-7113	39+00	290 IL53 KEEP LEFT	-	-	8.5	8.5	2	W6X15	630	1.4	156	-	-
HIG-GM-7201	25+13	EAST 290 SOUTH IL 53 KEEP RIGHT	9.0	8.0	9.0	8.0	2	W6X15	555	1.4	156	-	-
HIG-GM-7202	37+44	TO 90/NORTH 53 WEST IL 53, KEEP LEFT	10.5	10.5	10.5	10.5	2	W8X18	756	1.4	156	-	-
HIG-GM-7205	49+91	290 EAST/IL 53 SOUTH/CHICAGO	11.5	8.5	11.5	8.5	2	W8X18	756	1.4	156	2	2
HIG-GM-7210	52+00	290 EAST/IL 53 SOUTH/CHICAGO	11.5	8.5	11.5	8.5	2	W8X18	756	1.4	156	2	2
HIG-GM-7218	77+50	290 IL53 KEEP LEFT	-	-	9.0	8.0	2	W6X15	615	1.4	156	-	-
HIG-GM-7220	83+50	290 IL53 KEEP RIGHT	-	-	10.5	10.5	2	W8X18	828	1.4	156	-	-
WFR-GM-7522	24+77	IL RT 53 NORTH, 290 WEST, TO 90 TOLLWAY	11.0	11.5	11.0	11.5	2	W8X18	792	1.4	156	2	2
GLF-GM-7605	48+68	TO 90/290/IL 53, KEEP LEFT	9.5	10.0	9.5	10.0	2	W6X15	615	1.4	156	2	2
TOTALS									9,595	20	1,960	16	16

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC. ... LICENSE NO. ... CONTRACT NO. 60P24



USER NAME = 231uk4	DESIGNED - DJS	REVISED - 4-2-12 ADD 1
PLOT SCALE = 1/8"=1'-0"	DRAWN - LKB	REVISED -
PLOT DATE = 4/27/2012	CHECKED - RWL	REVISED -
	DATE - 12-13-11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

Rev. 4-12-12

*F.A.I. 290 (INTERSTATE 290)
*F.A.U. 342 (IL ROUTE 53)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2011-024-5G <td> <td>DUPAGE/COOK <td>132</td> <td>23</td> </td></td>	<td>DUPAGE/COOK <td>132</td> <td>23</td> </td>	DUPAGE/COOK <td>132</td> <td>23</td>	132	23
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P24	