

SUMMARY OF QUANTITIES

90% FED.  
10% STATE  
URBAN

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0021 SAFETY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	52	52
21101815	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,340	2,340
25000210	SEEDING, CLASS 2A	ACRE	0.48	0.48
25200110	SODDING, SALT TOLERANT	SQ YD	12	12
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	43	43
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	43	43
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	43	43
25100630	EROSION CONTROL BLANKET	SQ YD	2,328	2,328
42001300	PROTECTIVE GOAT	SQ YD	866	866
44003100	MEDIAN REMOVAL	SQ FT	5,424	5,424
48101820	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	3,083	3,083
50105220	PIPE CULVERT REMOVAL	FOOT	10	10
54213889	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2	2
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	18	18
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS	FOOT	502	502
63000017	STEEL PLATE BEAM GUARDRAIL, TYPE D, 6 FOOT POSTS	FOOT	175	175
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12	12
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	46	46
63200310	GUARDRAIL REMOVAL	FOOT	3,949	3,949
64300240	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	4	4
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	7	7
64301060	ATTENUATOR BASE	SQ YD	102	102
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MQ	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
78200420	GUARDRAIL MARKERS, TYPE B	EACH	103	103
78201000	TERMINAL MARKER DIRECT APPLIED	EACH	46	46
89502376	REBUILD EXISTING HANDHOLE	EACH	3	3
Z0004562	COMBINATION CONCRETE CURB & GUTTER, REMOVAL & REPLACEMENT	FOOT	2,598	2,598
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	154	154
Z0064800	SELECTIVE CLEARING	UNIT	0.36	0.36
X2503100	MOWING	UNIT	210	210
X8062100	STABILIZED MEDIAN SURFACE 12"	SQ YD	602	602

\* DENOTES SPECIALTY ITEM

△ Non-participating (100% State)

FILE NAME :	USER NAME : .USER.	DESIGNED : EF	REVISED :	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GUARDRAIL IMPROVEMENTS - NORTHERN COOK COUNTY SUMMARY OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	DRAWN : EF	REVISED :	2011-092-GRR			COOK	20	3		
PLOT SCALE : 100' / IN.	CHECKED : RS	REVISED :	VARIOUS ROUTES			CONTRACT NO. 60R20				
PLOT DATE : 2/6/2012	DATE : 02-07-2012	REVISED :	ILLINOIS FED. AID PROJECT							
				SCALE: 50	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.			