

INDEX OF SHEETS

1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-5	LOCATION MAPS
6-18	DRAINAGE REPAIR PLANS (SN 016-2504)
19-26	DRAINAGE REPAIR PLANS (SN 016-0337)
27	ARTERIAL ROAD INFORMATION SIGN (TC-22)

STATE STANDARDS

701601-07	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVARSABEL MEDIAN
701801-05	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-02	TRAFFIC CONTROL DEVICES
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 2' FROM PAVEMENT EDGE
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

DRAINAGE ADJUSTMENT OR RECONSTRUCTION LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED AT THE UNIT PRICE BID FOR THE WORK.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BRIDGE INSPECTORS.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

CONTRACTOR SHALL CONTACT MR. BILL MALLOY, DIRECTOR OF TERMINAL OPERATIONS, TO COORDINATE WORK WITH U.P. (UNION PACIFIC) FOR ACCESS TO YARD, SPECIFICALLY, THE AREA UNDER THE MANNHEIM RD. BRIDGE

PIERS 8, 9 AND 10 OF SN 016-2504 ARE LOCATED WITHIN FENCED METROPOLITAN WATER RECLAMATION DISTRICT PROPERTY. ARRANGEMENTS ARE TO BE MADE FOR ACCESSIBILITY.

THE CONTRACTOR SHALL PROVIDE MANLIFTS TO THE ENGINEER (OR ENGINEER'S DESIGNATED REPRESENTATIVE), AS REQUIRED IN NUMBER AND TYPE FOR THE ENGINEER'S USE IN INSPECTING THE VARIOUS ASPECTS OF THE CONTRACTORS WORK, COST SHALL BE INCLUDED IN THE CONTRACT PLAN.

THE CONTRACTORS SHALL SCHEDULE ANY PARTIAL OR COMPLETE CLOSURES OF PARKING AND STORAGE AREAS UNDER THE ELEVATED BRIDGE WHEN BELOW DECK OPERATIONS ARE BEING CONDUCTED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SCHEDULE ANY SUCH CLOSURES WITH THE AFFECTED PARTIES. ANY CONTRACTOR INFLICTED DAMAGES TO VEHICLES AND OTHER PROPERTIES UNDER ELEVATED BRIDGES WILL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

*1) FAJ 2612
2) FAP 330

FILE NAME =	USER NAME = curryw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS GENERAL NOTES		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pvc\work\pavdat\curryw\0924649\01322	2-Dasgr.dgn	DRAWN -	REVISED -		#	2012-001-1	COOK	27	2		
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.		CONTRACT NO. 60Y31				
	PLOT DATE = 3/2/2012	DATE -	REVISED -		ILLINOIS FED. AID PROJECT						