CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 100% VILLAGE — WATERMAIN IMPROVEMENTS 0043	CONSTRUCTION CODE: STP FUNDS 75% FEDERAL/25% VILLAGE — ROADWAY IMPROVEMENTS 0004	CONSTRUCTION CODE: STP FUNDS 75% FEDERAL/25% VILLAGE — TRAINING 0042
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	63		63	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	228		228	
20101000	TEMPORARY FENCE	FOOT	600		600	
20101700	SUPPLEMENTAL WATERING	UNIT	3.0		3.0	
20200100	EARTH EXCAVATION	CU YD	9180		9180	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1065		1065	
20800150	TRENCH BACKFILL	CU YD	2554	1914	640	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5542		5542	
25000110	SEEDING, CLASS 1A	ACRE	1.25		1.25	
25100125	MULCH, METHOD 3	ACRE	0.75		0.75	
25100630	EROSION CONTROL BLANKET	SQ YD	2380		2380	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150		150	
28000400	PERIMETER EROSION BARRIER	FOOT	5225		5225	
28000510	INLET FILTERS	EACH	40		40	
28100105	STONE RIPRAP, CLASS A3	SQ YD	22		22	
30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	SQ YD	19,825		19825	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	134		134	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	239		239	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	305		305	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13,970		13970	
40600300	AGGREGATE (PRIME COAT)	TON	26		26	
40600895	CONSTRUCTING TEST STRIP	EACH	2		2	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	42		42	
40701876	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9-3/4"	SQ YD	17,195		17195	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	435		435	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8234		8234	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1000		1000	
42400800	DETECTABLE WARNINGS	SQ FT	222		222	
44000100	PAVEMENT REMOVAL	SQ YD	15682		15682	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	929		929	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7810		7810	
44000600	SIDEWALK REMOVAL	SQ FT	9549		9549	

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 100% VILLAGE — WATERMAIN IMPROVEMENTS 0043	CONSTRUCTION CODE: STP FUNDS 75% FEDERAL/25% VILLAGE — ROADWAY IMPROVEMENTS 0004	CONSTRUCTION CODE: STP FUNDS 75% FEDERAL/25% VILLAGE — TRAINING 0042
	44004250	PAVED SHOULDER REMOVAL	SQ YD	221		221	
	44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	40	40		
	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	28	28		
	44213200	SAW CUTS	FOOT	127	127		
	50102400	CONCRETE REMOVAL	CU YD	10.0		10.0	
	50105220	PIPE CULVERT REMOVAL	FOOT	25		25	
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2		2	
	54247090	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	2		2	
	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	2277		2277	
	550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	499		499	
	550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	37		37	
	550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	31		31	
	550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	586		586	
*	56103000	DUCTILE IRON WATERMAIN 6"	FOOT	20	20		
*	56103100	DUCTILE IRON WATERMAIN 8"	FOOT	422	422		
*	56103200	DUCTILE IRON WATERMAIN 10"	FOOT	3231	3231		
*	56105000	WATER VALVES 8"	EACH	8	8		
*	56105100	WATER VALVES 10"	EACH	11	11		
*	56200300	WATER SERVICE LINE 1"	FOOT	747	747		
*	56200700	WATER SERVICE LINE 2"	FOOT	30	30		
*	56201160	WATER SERVICE LINE 6"	FOOT	50	50		
*	56400200	FIRE HYDRANTS TO BE MOVED (SPECIAL)	EACH	3		3	
*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	14	14		
	60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	5		5	
	60200310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	2		2	
	60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	3		3	
	60207105	CATCH BASINS, TYPE C, TYPE 3 FRAME AND GRATE	EACH	6		6	
	60207115	CATCH BASINS, TYPE C, TYPE 3V FRAME AND GRATE	EACH	7		7	
	60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	6		6	
	60207915	CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	4		4	
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	14		14	
	60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7		7	

REVISED: FEBRUARY 7, 2012
REVISED: DECEMBER 30, 2011

FILE NAME: XXX

GERALD L. HEINZ & ASSOCIATES, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
206 NORTH RIVER STREET
EAST DUNDEE, ILLINOIS 60118

USER NAME:
PLOT SCALE: NTS
PLOT DATE:

DESIGNED: EBW
DRAWN: PC
CHECKED: JDH
DATE: AUGUST 25, 2010

REVISED: MARCH 23, 2011
REVISED: MAY 16, 2011
REVISED: JUNE 2, 2011
REVISED: JULY 20, 2011

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: 1"= 20' | SHEET NO. 1 OF 2 SHEETS | STA: TO STA:

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2528	04-00043-00-PV	KANE	85	3

CONTRACT NO. 63507

FED. ROAD DIST. NO. | ILLINOIS | FED. AID. PROJECT