

PI#	ITEM DESCRIPTION	SPECIAL PROVISION	SPECIALTY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
						ROADWAY	TRAFFIC SIGNALS
88500100	INDUCTIVE LOOP DETECTOR		X	EACH	9		9
88600100	DETECTOR LOOP, TYPE I		X	FOOT	437		437
88800100	PEDESTRIAN PUSH-BUTTON		X	EACH	6		6
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION		X	EACH	1		1
89500100	RELOCATE EXISTING SIGNAL HEAD		X	EACH	3		3
89501300	RELOCATE EXISTING MAST ARM ASSEMBLY AND POLE		X	EACH	1		1
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM DETECTOR UNIT	*	X	EACH	1		1
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM PHASING UNIT	*	X	EACH	1		1
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT		X	FOOT	1088		1088
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT		X	FOOT	713		713
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	*	X	EACH	1		1
89502380	REMOVE EXISTING HANDHOLE	*	X	EACH	1		1
89502385	REMOVE EXISTING CONCRETE FOUNDATION	*	X	EACH	3		3
Z0004542	HOT-MIX ASPHALT REMOVAL (SPECIAL)	*		SQ YD	1484	1484	
Z0013798	CONSTRUCTION LAYOUT	*		L SUM	1	1	
Z0030850	TEMPORARY INFORMATION SIGNING	*		SQ FT	51		51
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	*	X	CAL MO	3		3
Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	*	X	EACH	1		1
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	*		CU YD	50	50	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	*	X	EACH	1		1
X0322915	METAL LIGHT POLE, INSTALL ONLY	*	X	EACH	2		2
X0326884	BRICK SIDEWALK REMOVAL	*		SQ FT	1194	1194	
X0540000	BRICK PAVERS	*		SQ FT	100	100	
X8100105	CONDUIT SPLICE	*	X	EACH	1		1
X8410105	TEMPORARY LIGHTING SYSTEM	*	X	EACH	1		1
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	*	X	EACH	1		1
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	*	X	EACH	1		1
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	*	X	FOOT	243		243
XX001388	PULL EXISTING CABLE FROM UNIT DUCT	*	X	FOOT	55		55
XX002094	REMOVE AND REINSTALL FIBER OPTIC CABLE IN CONDUIT	*	X	L SUM	1		1
XX004688	BRICK PAVER SIDEWALK	*		SQ FT	970	970	
XX007259	SIGN AND POST REMOVAL	*		EACH	2	2	
XX007729	DETECTABLE WARNINGS, SPECIAL	*		SQ FT	72	72	
66900200	NON-SPECIAL WASTE DISPOSAL	*	X	CU YD	5		5
66900450	SPECIAL WASTE PLANS AND REPORTS	*	X	L SUM	1		1
66900530	SOIL DISPOSAL ANALYSIS	*	X	EACH	1		1

△