

SUMMARY OF QUANTITIES		LOCATION OF WORK		GENEVA ROAD AT SCHMALE ROAD/MAIN STREET	GENEVA ROAD AT PRESIDENT STREET	GENEVA ROAD AT BLOOMINGDALE ROAD	GENEVA ROAD AT KENILWORTH AVENUE/CHURCHILL SCHOOL	GENEVA ROAD AT WESTERN AVENUE	GENEVA RD / ST. CHARLES RD AT MAIN STREET/ GLEN ELLYN ROAD	ST. CHARLES ROAD AT RIFORD ROAD/ ACKERMAN PARK	ST. CHARLES ROAD AT SWIFT ROAD	GLEN ELLYN ROAD AT ARMITAGE AVENUE	GLEN ELLYN ROAD AT MID-BLOCK CROSSING	GLEN ELLYN ROAD AT FULLERTON AVENUE	GLEN ELLYN ROAD AT WINDY POINT DRIVE	GLEN ELLYN ROAD AT GREGORY AVENUE	GLEN ELLYN ROAD AT ARMY TRAIL ROAD	GENEVA RD & ST. CHARLES RD INTERCONNECT - FROM SCHMALE RD/MAIN ST TO SWIFT RD	GLEN ELLYN RD INTERCONNECT - FROM ARMITAGE AVE TO ARMY TRAIL RD	
				0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021
CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODES																
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	322									322								
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	912		18				19			47	686	41				101		
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	4						1				1					2		
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	9				1						3	2				3		
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	5		2	2												1		
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1										1							
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	2										2							
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16						4				4					8		
87800205	MODIFY EXISTING TYPE "D" FOUNDATION	EACH	1										1							
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30										30							
87900200	DRILL EXISTING HANDHOLE	EACH	41						1				17					2	10	11
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	18		2				4			3	4	2				3		
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10		1				2			1	2					4		
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1									1								
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	8		4							1	2					1		
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	8						4				2	2						
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	8		4							2	1					1		
88030330	SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION, 1-5 SECTION BRACKET MOUNTED	EACH	1										1							
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	14						2			2		2		4		4		
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	11		4				3				4							
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	26		6				4			4	6	2				4		
88500100	INDUCTIVE LOOP DETECTOR	EACH	21						4			5	7					5		
88600100	DETECTOR LOOP, TYPE I	FOOT	340										340							
88700200	LIGHT DETECTOR	EACH	2										2							
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1										1							
88800100	PEDESTRIAN PUSH-BUTTON	EACH	28		4				4			2	8	2		4		4		
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	4			4														
89500120	REMOVE EXISTING SERVICE INSTALLATION	EACH	9		1	1	1	1	1			1	1	1		1		1		
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	4						1			1		1				1		
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,434						393			238	803							
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	10		1	1	1	1	1			1	1	1		1		1		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	4										4							
X8570015	CONTROLLER (SPECIAL)	EACH	1							1										
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	3	1						1								1		
XX003665	REBUILD EXISTING HANDHOLE TO DOUBLE HANDHOLE	EACH	1										1							
Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	13															8		5
* * Z0076600	TRAINEES	HOUR	500																	

\* SPECIALTY ITEM  
 \* \* CONSTRUCTION CODE OF 0042