

CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ITEP 0031 80% FEDERAL 20% LOCAL	RECONSTRUCT 0004 80% FEDERAL 20% LOCAL
20100110	TREE REMOVAL (6 TO 15 UNIT DIAMETER)	UNIT	24	24	
~ 20200100	EARTH EXCAVATION	CUYD	200	200	
~ * 21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQYD	525	525	
~ * 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQYD	950	950	
~ * 21101805	COMPOST FURNISH AND PLACE, 2"	SQYD	510	510	
* 25200100	SODDING	SQYD	950	950	
* 25200200	SUPPLEMENTAL WATERING	UNIT	50		50
~ 31101180	SUBBASE GRANULAR MATERIAL, TYPE B 2"	SQYD	1,400	1,400	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	155	155	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	50	50	
~ 42101300	PROTECTIVE COAT	SQYD	1,780	1,780	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	75	75	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SOFT	7,000	7,000	
~ 42400800	DETECTABLE WARNINGS	SOFT	160	160	
44000100	PAVEMENT REMOVAL	SQYD	330		330
~ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	175	175	
~ 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	650	650	
~ 44000600	SIDEWALK REMOVAL	SOFT	2,900	2,900	
55100400	STORMSEWER REMOVAL 10"	FOOT	5		5
~ 60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1
~ 60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2	
60300805	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3	
~ 60500050	REMOVING CATCH BASINS	EACH	1		1
~ 60600605	CONCRETE CURB, TYPE B	FOOT	1,840		1,840
60619121	CONCRETE MEDIAN, TYPE SB-6	SQFT	545		545
67100100	MOBILIZATION	LSUM	1	1	
* 72000100	SIGN PANEL - TYPE 1	SQFT	20	20	
* 72900100	METAL POST - TYPE A	FOOT	65	65	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,315	2,315	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	705	705	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	185	185	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100	100	
* 81028150	UNDERGROUND CONDUIT, GALVANIZED STEEL, 1/2" DIA.	FOOT	520	520	
* 8102540	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 3-1/C NO.10	FOOT	400	400	
~ * A2000320	TREE, ACER MIYABEI MORTON (STATE STREET MIYABEI MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	16	16	
~ * A2000332	TREE, ACER MIYABEI MORTON (STATE STREET MIYABEI MAPLE), 4" CALIPER, BALLED AND BURLAPPED	EACH	4	4	
~ * A2002860	TREE, CELTIS OCCIDENTALIS CHICAGOLAND, (CHICAGOLAND HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7	7	
~ * A2002886	TREE, CELTIS OCCIDENTALIS CHICAGOLAND, (CHICAGOLAND HACKBERRY), 4" CALIPER, BALLED AND BURLAPPED	EACH	2	2	
~ * A2004420	TREE, GINKGO BILOBA AUTUMN GOLD (AUTUMN GOLD GINKGO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7	7	
~ * A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6	6	
~ * A2005030	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 4" CALIPER, BALLED AND BURLAPPED	EACH	6	6	
~ * A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7	7	
~ * A2006532	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 4" CALIPER, BALLED AND BURLAPPED	EACH	3	3	
~ * A2007920	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	17	17	

CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ITEP 0031 80% FEDERAL 20% LOCAL	RECONSTRUCT 0004 80% FEDERAL 20% LOCAL
~ * A2007932	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 4" CALIPER, BALLED AND BURLAPPED		2	2	
~ * A2008519	TREE, ULMUS MORTON GLOSSY (TRIUMPH ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	11	11	
~ * A2008626	TREE, ULMUS MORTON GLOSSY (TRIUMPH ELM), 4" CALIPER, BALLED AND BURLAPPED	EACH	5	5	
~ * A2012005	TREE, AESCULUS X CARNEA FORT MCNAIR (FORT MCNAIR RED HORSECHESTNUT), 4" CALIPER, BALLED AND BURLAPPED, MATCHING HEADS	EACH	19	19	
~ * B2000774	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	7	7	
~ * B2002220	TREE, CRATAEGUS VIRIDIS WINTER KING (WINTER KING GREEN HAWTHORN), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	7	7	
~ * B2006332	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 4" CALIPER, BALLED AND BURLAPPED	EACH	30	30	
~ * K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	43	43	
~ * K1001988	IRRIGATION SYSTEM SPECIAL	LSUM	1	1	
~ Z0027900	GEOTECHNICAL FABRIC (FILTER CLOTH)	SQYD	110	110	
~ X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	40	40	
~ X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	550		550
~ X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1	1	
~ XX008615	SAFETY CHAIN	FOOT	120	120	
~ XX000541	EXPLORATORY EXCAVATION	CUYD	100	100	
~ XX000959	TRASH RECEPTACLES	EACH	2	2	
~ LR430050	CONCRETE PAVER SIDEWALK	SQYD	115	115	
~ XX005735	PLANTER CURB	FOOT	1,700		1,700
~ XX005878	CAST IRON TREE GRATES	EACH	7	7	
~ * XX006834	ELECTRICAL CONNECTION TO EXISTING LIGHTING SYSTEM	EACH	1	1	
~ XX007399	MONUMENT TYPE A FOUNDATION	EACH	18	18	
~ XX007400	MONUMENT TYPE B FOUNDATION	EACH	2	2	
~ XX007401	MONUMENT TYPE C FOUNDATION	EACH	2	2	
~ * XX008160	DECORATIVE LIGHTING SYSTEM COMPLETE	LSUM	1	1	
~ XX008203	CONCRETE RETAINING WALL	SOFT	550	550	
~ Z0003855	BICYCLE RACKS	EACH	2	2	
~ Z0004002	BOLLARDS	EACH	28	28	
~ Z0004542	HOT-MIX ASPHALT REMOVAL (SPECIAL)	SQYD	1,600		1,600
~ * Z0073900	TENSION WIRE, SPECIAL	FOOT	1,000	1,000	
~ Z0076600	TRAINEES	HOUR	500	500	
~ * XX008605	STEEL SUPPORT POLE FOR OVERHEAD LIGHT STRANDS, 19 FOOT	EACH	18	18	
~ * XX008606	VERTICAL ELEMENT, 22 FOOT 6 INCH	EACH	2	2	
~ * XX008607	VERTICAL ELEMENT, 35 FOOT	EACH	2	2	

* DENOTES SPECIALTY ITEM
~ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\60011046 - Division Street ITEP\Sum-Qty-2007.dwg Feb 03, 2012 - 2:53pm

HANCOCK ENGINEERING
◆ Civil Engineers
◆ Municipal Consultants
◆ Established 1911

9933 Roseville Road
Westchester, Illinois 60154-2780
Phone: 708/965-0390
Fax: 708/965-1712

DESIGNED - ELS	REVISED -
DRAWN - MK, DMM	REVISED -
CHECKED - ELS	REVISED -
DATE - 02-06-12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1026	10-00116-00-SW	COOK	40	4
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 63854	
FED. AID PROJECT M-TE-001(825)			EHE PROJECT NO. 600-11-04602	