

SUMMARY OF QUANTITIES

ITEM NO.	PAY ITEM	UNIT	CONSTRUCTION TYPE CODE
			0005
			TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	47
20800150	TRENCH BACKFILL	CU YD	72
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,122
40600300	AGGREGATE (PRIME COAT)	TON	84
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,658
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	358
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3,462
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	2,232
42400800	DETECTABLE WARNINGS	SQ FT	470
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	39,472
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,232
44000800	SIDEWALK REMOVAL	SQ FT	3,336
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	16
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	1,181
44300200	STRIP REFLECTIVE CRACK CONTROL	FOOT	15,629
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 1/2"	FOOT	240
55100500	STORM SEWER REMOVAL 12"	FOOT	240
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7
60237000	INLETS, TYPE A, TYPE 15 FRAME AND LID	EACH	14
60240320	INLETS, TYPE B, TYPE 15 FRAME AND LID	EACH	2
60280100	INLETS TO BE ADJUSTED	EACH	20
60404300	FRAMES AND GRATES, TYPE 3	EACH	1
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	22
60406400	FRAMES AND LIDS, TYPE 15	EACH	1
60500060	REMOVING INLETS	EACH	23
67100100	MOBLIZATION	L SUM	1
# 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
# 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
# 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,396
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	400
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	360
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8,617
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,178
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,479
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	105
* # 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
* # 88600100	DETECTOR LOOP, TYPE I	FOOT	75
# X4240430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH. SPECIAL	SQ FT	3,968
# X4400196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	1,737
# X8026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	5
# X8030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17
# XX007278	PARKWAY RESTORATION	SQ YD	1,772
# Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	104
# Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	4,087

INDICATES ITEM COVERED BY SPECIAL PROVISION
 * INDICATES SPECIALTY ITEM

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC. \\s05cfe\c\soft\hr\dep\cfe\c\lch
 LICENSE NO. 184-000211 - EXPIRES 4/30/2013
 IN:\C\soft\lone\PRK\T\091213_00-2002_Summary of Quantities.dwg
 5:08:00 PM 2/6/2012 4:27:26 PM



DESIGNED - TMS	REVISED -
DRAWN - KAR	REVISED -
CHECKED - JJF	REVISED -
DATE - 10-26-11	FILE - 091213-S00.shx

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE STA. TO STA.

*1055/1056

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	11-00095-00-RS	COOK	27	3
FED. ROAD DIST. NO. ILLINOIS/FED. AID PROJECT M-9003(969)			CONTRACT NO. 63690	