

SCHEDULE OF MATERIALS

SIDEWALK AND DETECTABLE WARNING SCHEDULE												
	Station	O/S	Sidewalk Removal (SQ FT)	PCC Sidewalk 5 Inch, Special (SQ FT)	Detectable Warnings (SQ FT)		Station	O/S	Sidewalk Removal (SQ FT)	PCC Sidewalk 5 Inch, Special (SQ FT)	Detectable Warnings (SQ FT)	
Lakewood Blvd	13+39	LT		75.0	10.0	Indianwood Blvd	106+68	RT	151.0	151.0	10.0	
	13+39	RT		75.0	10.0		106+68	MED	45.0	45.0	20.0	
Lakewood Blvd	13+92	LT	87.0	87.0	10.0	106+68	LT	50.0	50.0	10.0		
	14+63	LT	106.0	106.0	10.0	120+50	LT		940.0			
	17+17	RT	63.0			121+43	LT	60.0				
	17+22	RT	35.0	35.0	10.0	121+43	MED	24.0				
	17+53	RT	35.0	35.0	10.0	121+43	RT	61.0				
	17+61	RT	40.0	40.0	10.0	126+58	RT	71.0				
	17+61	LT		75.0	10.0	126+63	RT	25.0	25.0	10.0		
	22+91	LT	69.0			126+99	RT	196.0	196.0	10.0		
	22+99	LT	25.0	25.0	10.0	129+92	RT	86.0				
	23+44	LT	69.0			130+29	MED	63.0				
	23+64	LT	73.0	73.0	10.0	130+56	LT	25.0	25.0	10.0		
	23+64	RT	73.0	73.0	10.0	130+65	RT	100.0	100.0	10.0		
	26+42	LT	72.0	72.0		131+95	RT	25.0	25.0	10.0		
	29+71	RT	49.0	49.0	10.0	131+90	LT	25.0	25.0	10.0		
	29+71	LT		75.0	10.0	134+85	RT	101.0	101.0			
	29+74	RT	30.0	30.0	10.0	136+51	RT	113.0				
	30+06	RT	30.0	30.0	10.0	136+60	RT	25.0	25.0	10.0		
	30+12	RT	68.0			136+96	RT	25.0	25.0	10.0		
	32+34	RT	35.0	35.0	10.0	137+06	RT	25.0	25.0	10.0		
	32+66	RT	25.0	25.0	10.0	137+02	LT	25.0	25.0	10.0		
	34+92	LT	192.0	192.0	20.0	141+10	LT	127.0				
	34+86	RT	35.0	35.0	10.0	141+47	RT	126.0				
	34+92	RT	30.0	30.0	10.0	141+50	LT		532.0	10.0		
	35+33	RT	30.0	30.0	10.0	141+98	RT		86.0	10.0		
	35+62	RT	35.0	35.0	10.0							
	35+67	LT	30.0	30.0	10.0							
	35+58	LT	25.0	25.0	10.0							
	48+07	LT	30.0	30.0	10.0							
	48+07	RT	30.0	30.0	10.0							
	48+12	RT	25.0	25.0	10.0							
	48+49	RT	112.0									
	55+33	RT	114.0									
	55+38	RT	30.0	30.0	10.0							
	55+70	RT	25.0	25.0	10.0							
	55+76	RT	35.0	35.0	10.0							
	SUBTOTALS:			1762.0	1567.0	310.0	SUBTOTALS:			1574.0	2401.0	160.0

DRIVEWAYS SCHEDULE				
	Station	o/s	Driveway Pavement Removal (SQ YD)	PCC Driveway Pavement, 6" (SQ YD)
LAKEWOOD BLVD	13+17	RT	19.5	19.5
	14+02	RT	29.1	29.1
	14+74	RT	20.5	20.5
	17+41	LT	19.7	19.7
	18+27	LT	16.7	16.7
	19+22	RT	29.2	29.2
	21+17	LT	18.7	18.7
	21+36	RT	28.2	28.2
	21+58	LT	25.2	25.2
	23+37	RT	25.7	25.7
	24+49	RT	22.2	22.2
	24+79	RT	15.4	15.4
	25+50	RT	35.5	35.5
	28+93	RT	15.3	15.3
	30+20	LT	22.2	22.2
	30+45	LT	22.2	22.2
	31+26	RT	20.4	20.4
	32+12	LT	17.1	17.1
	32+34	LT	18.8	18.8
	33+94	LT	18.9	18.9
	34+28	RT	42.6	42.6
	36+27	RT	55.4	55.4
	37+04	LT	66.6	66.6
	38+00	LT	77.3	77.3
	38+98	LT	35.6	35.6
	39+43	LT	68.7	68.7
	39+82	RT	29.9	29.9
	40+77	RT	29.9	29.9
	41+99	RT	29.9	29.9
	42+26	RT	55.4	55.4
	44+22	LT	57.7	57.7
	45+42	LT	37.0	37.0
	45+84	LT	52.2	52.2
45+85	RT	57.8	57.8	
46+55	LT	53.2	53.2	
46+82	LT	54.4	54.4	
49+81	RT	78.7	78.7	
50+77	RT	41.9	41.9	
51+03	RT	44.3	44.3	
51+95	RT	46.6	46.6	
53+41	RT	52.2	52.2	
55+23	LT	73.8	73.8	
56+52	LT	73.8	73.8	
58+33	LT	74.5	74.5	
SUBTOTALS:			1730.0	1730.0
INDIANWOOD BLVD	105+71	RT	21.7	21.7
	106+52	RT	27.3	27.3
	108+43	LT	17.9	17.9
	408+62	LT	25.5	25.5
	109+84	LT	22.6	22.6
	111+64	LT	25.4	25.4
	113+35	RT	22.5	22.5
	117+92	LT	11.5	11.5
	122+68	LT	118.7	118.7
	123+48	RT	56.3	56.3
	128+20	LT	135.2	135.2
129+46	RT	17.0	17.0	
SUBTOTALS:			502.0	502.0

CLASS D PATCHING								
	STATION	TO STATION	LENGTH	WIDTH	AREA (SQ YD)	Type III (Sq Yd)	Type IV (Sq Yd)	
LAKEWOOD BLVD	23+03	22+86	17.0	36.0	68.0		68.0	
	36+70	35+77	93.0	15.0	155.0		155.0	
	46+75	46+53	22.0	11.0	26.9		26.9	
	SUBTOTAL:						0.0	250.0
INDIANWOOD BLVD	102+67	103+16	49.0	7.0	38.2		38.2	
	102+20	102+88	68.0	10.0	75.6		75.6	
	102+67	103+19	52.0	21.0	121.4		121.4	
ST SEWER	105+58	105+85	27.0	21.0	63.0		63.0	
	105+85	106+80	95.0	10.0	105.6		105.6	
	105+68	105+98	30.0	21.0	70.0		70.0	
	117+58	118+11	53.0	21.0	123.7		123.7	
	117+62	118+55	93.0	20.0	206.7		206.7	
	118+11	118+55	44.0	11.0	53.8		53.8	
	128+20	128+33	13.0	11.0	15.9	15.9		
	129+28	129+48	20.0	16.0	35.6		35.6	
	140+20	140+50	30.0	11.0	36.7		36.7	
	SUBTOTAL:						16.0	931.0
	TOTAL:						16.0	1181.0

INLETS TO BE ADJUSTED				
	Station	O/S	Description of Work	
LAKEWOOD BLVD	17+69	RT	MORTAR	
	20+26	RT	MORTAR	
	23+17	RT	MORTAR	
	25+00	LT	MORTAR	
	26+08	RT	MORTAR	
	29+66	RT	MORTAR	
	29+98	LT	MORTAR	
	30+22	RT	MORTAR	
	38+35	LT	MORTAR	
	45+00	RT	MORTAR	
	48+28	LT	MORTAR	
	57+60	LT	MORTAR	
	57+60	RT	MORTAR	
	Subtotal:			13
	INDIANWOOD BLVD	111+55	LT	RESET FRAME/CURB
111+46		RT	RESET FRAME/CURB	
127+39		LT	RESET FRAME/CURB	
131+73		LT	RESET FRAME/CURB	
134+92		LT	MORTAR	
138+47		LT	RESET FRAME/CURB	
138+45		RT	RESET FRAME/CURB	
Subtotal:			7	

SANITARY MANHOLES TO BE ADJUSTED			
	Station	O/S	
LAKEWOOD BLVD	23+17	LT	
	58+64	LT	
	59+32	RT	
	Subtotal:		
INDIANWOOD BLVD	109+80	LT	
	117+97	LT	
	Subtotal:		

INLETS TO BE REMOVED AND REPLACED				
	STATION	O/S	TYPE	CASTING
LAKEWOOD BLVD	17+08	RT	A	TYPE 15 FRAME AND LID
	17+33	LT	A	TYPE 15 FRAME AND LID
	20+12	LT	A	TYPE 15 FRAME AND LID
	23+50	LT	B	TYPE 15 FRAME AND LID
	26+08	LT	A	TYPE 15 FRAME AND LID
	35+07	LT	A	TYPE 15 FRAME AND LID
	34+96	RT	A	TYPE 15 FRAME AND LID
	35+40	RT	A	TYPE 15 FRAME AND LID
	35+53	LT	A	TYPE 15 FRAME AND LID
	41+67	LT	A	TYPE 15 FRAME AND LID
	41+68	RT	A	TYPE 15 FRAME AND LID
	45+00	LT	B	TYPE 15 FRAME AND LID
	47+99	RT	A	TYPE 15 FRAME AND LID
	52+06	LT	A	TYPE 15 FRAME AND LID
	55+39	RT	A	TYPE 15 FRAME AND LID
55+60	LT	A	TYPE 15 FRAME AND LID	
INDIANWOOD BLVD	105+89	RT	A	TYPE 3 FRAME AND GRATE
	105+94	RT	A	TYPE 3 FRAME AND GRATE
	105+73	LT	A	TYPE 3 FRAME AND GRATE
	105+98	LT	A	TYPE 3 FRAME AND GRATE
	127+11	RT	A	TYPE 3 FRAME AND GRATE
	134+92	RT	A	TYPE 3 FRAME AND GRATE
	136+58	RT	A	TYPE 3 FRAME AND GRATE
	Subtotal: 6			

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)		
	Station	O/S
LAKEWOOD BLVD	14+60	LT
	30+02	RT
	35+25	RT
	37+66	LT
	46+71	RT
	48+25	LT
Subtotal: 6		
INDIANWOOD BLVD	124+00	LT
	127+02	RT
	127+28	LT
	129+00	CL
	130+58	RT
	131+23	LT
	134+00	CL
	134+99	CL
Subtotal: 11		

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 1100 N. WASHINGTON ST., SUITE 200, DEERFIELD, IL 60015
 TEL: 847.934.1000 FAX: 847.934.1001
 PROJECT: 11-00095-00-RS
 SHEET: 27 OF 44
 DATE: 10/26/11



DESIGNED - TMS	REVISED -
DRAWN - KAR	REVISED -
CHECKED - JJJ	REVISED -
DATE - 10-26-11	FILE - 091213-S00.shp

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF MATERIALS

SCALE: NONE

STA. TO STA.

*1055/1056

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	11-00095-00-RS	COOK	27	4
COORDINATOR: INQ. 63690				
FED. ROAD DIST. NO. ILLINOIS/FED. AID PROJECT M-900319691				