

**SUMMARY OF QUANTITIES**

| SPECIALTY ITEMS<br>(Δ) | SPECIAL PROVISION<br>(*) | PAY ITEM NUMBER | PAY ITEM DESCRIPTION                             | UNITS  | TOTAL QUANTITY | ROADWAY<br>80% FEDERAL<br>20% LOCAL<br>0005 |
|------------------------|--------------------------|-----------------|--|--------|----------------|---|
|                        |                          | 40600100        | BITUMINOUS MATERIALS (PRIME COAT)                | GALLON | 3,745          | 3,745                                       |
|                        |                          | 40600300        | AGGREGATE (PRIME COAT)                           | TON    | 76             | 76  |
|                        |                          | 40600982        | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT     | SQ YD  | 590            | 590   |
|                        |                          | 40600625        | LEVELING BINDER (MACHINE METHOD), N50            | TON    | 1,670          | 1,670                                       |
|                        |                          | 40603335        | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50     | TON    | 3,395          | 3,395                                       |
|                        |                          | 44000153        | HOT-MIX ASPHALT SURFACE REMOVAL, 1"              | SQ YD  | 38,560         | 38,560                                      |
|                        |                          | 44201741        | CLASS D PATCHES, TYPE II, 8 INCH                 | SQ YD  | 100            | 100   |
|                        |                          | 44201745        | CLASS D PATCHES, TYPE III, 8 INCH                | SQ YD  | 140            | 140   |
|                        |                          | 44201747        | CLASS D PATCHES, TYPE IV, 8 INCH                 | SQ YD  | 140            | 140   |
|                        |                          | 48101200        | AGGREGATE SHOULDERS, TYPE B                      | TON    | 818            | 818   |
|                        |                          | 60255500        | MANHOLES TO BE ADJUSTED                          | EACH   | 1              | 1   |
|                        |                          | 67100100        | MOBILIZATION                                     | L SUM  | 1              | 1   |
|                        |                          | 70102620        | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501  | L SUM  | 1              | 1   |
|                        |                          | 70300100        | SHORT TERM PAVEMENT MARKING                      | FOOT   | 5,730          | 5,730                                       |
| Δ                      |                          | 78000200        | THERMOPLASTIC PAVEMENT MARKING - LINE 4"         | FOOT   | 25,037         | 25,037                                      |
| Δ                      |                          | 78000650        | THERMOPLASTIC PAVEMENT MARKING - LINE 24"        | FOOT   | 48             | 48  |
|                        | *                        | Z0030850        | TEMPORARY INFORMATION SIGNING                    | SQ FT  | 128.50         | 128.50                                      |
|                        | *                        | X4401198        | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH  | SQ YD  | 585            | 585   |
|                        | *                        | XX006947        | HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT | SQ YD  | 985            | 985   |