

**SCHEDULE OF QUANTITIES
EAST WONDER LAKE ROAD**

HOT-MIX ASPHALT SURFACE REMOVAL – BUTT JOINT

LOCATION	WIDTH (FT)	LENGTH (FT)	AREA (SF)	AREA (SY)
SOUTH OF OAKWOOD (BEGIN PROJECT)	30.0	4.50	135.0	15.0
OAKWOOD DR	22.0	4.50	99.0	11.0
WOODED SHORE	18.0	4.50	81.0	9.0
WOODED SHORE	31.0	4.50	139.5	15.5
BEAVER RD	23.0	4.50	103.5	11.5
HICKORY GROVE RD	35.0	4.50	157.5	17.5
BEACH RD	30.0	4.50	135.0	15.0
PHEASANT RD	25.0	4.50	112.5	12.5
ORCHARD RD	26.0	4.50	117.0	13.0
HICKORY TR	48.0	4.50	216.0	24.0
HICKORY RD	23.0	4.50	103.5	11.5
ARBOR RD	22.0	4.50	99.0	11.0
OAK ST	30.0	4.50	135.0	15.0
CEDAR RD	26.0	4.50	117.0	13.0
DEEP SPRINGS RD	35.0	4.50	157.5	17.5
NORTH OF DEEP SPRINGS (END PROJECT)	30.0	4.50	135.0	15.0
TOTALS =			2,044.00	228.00

THERMOPLASTIC PAVEMENT MARKING – LINE 4"

LOCATION	STA	OFFSET	TO STA	OFFSET	LENGTH (FT)	TYPE	NET LENGTH (FT)
PRWOND	102+36.0	0.0	106+81.0	0.0	445.0	SK DA	112.0
PRWOND	107+65.0	0.0	111+41.0	0.0	376.0	SK DA	94.0
PRWOND	112+25.0	0.0	116+89.0	0.0	464.0	SK DA	116.0
PRWOND	116+89.0	0.0	120+15.0	0.0	326.0	SOLID SKIP	408.0
PRWOND	120+94.0	0.0	122+54.0	0.0	160.0	SOLID SKIP	200.0
PRWOND	127+29.0	0.0	130+46.0	0.0	317.0	SOLID SKIP	397.0
PRWOND	131+37.0	0.0	133+16.0	0.0	179.0	SOLID SKIP	224.0
PRWOND	133+90.0	0.0	135+36.0	0.0	146.0	SK DA	37.0
PRWOND	135+36.0	0.0	136+34.0	0.0	98.0	SOLID SKIP	123.0
PRWOND	137+19.0	0.0	139+30.0	0.0	211.0	SOLID SKIP	264.0
PRWOND	140+23.0	0.0	142+23.0	0.0	200.0	SOLID SKIP	250.0
PRWOND	143+14.0	0.0	144+29.0	0.0	115.0	SOLID SKIP	144.0
PRWOND	102+36.0	-12.0	106+81.0	-12.0	445.0	SOLID	445.0
PRWOND	102+36.0	12.0	111+41.0	12.0	905.0	SOLID	905.0
PRWOND	107+65.0	-12.0	111+41.0	-12.0	376.0	SOLID	376.0
PRWOND	112+25.0	-12.0	120+15.0	-12.0	790.0	SOLID	790.0
PRWOND	112+25.0	12.0	123+33.0	12.0	1,108.0	SOLID	1,108.0
PRWOND	120+94.0	-12.0	123+33.0	-12.0	239.0	SOLID	239.0
PRWOND	124+30.0	-12.0	126+60.0	-12.0	230.0	SOLID	230.0
PRWOND	124+30.0	12.0	133+16.0	12.0	886.0	SOLID	886.0
PRWOND	127+29.0	-12.0	130+46.0	-12.0	317.0	SOLID	317.0
PRWOND	131+36.0	-12.0	133+15.0	-12.0	179.0	SOLID	179.0
PRWOND	133+89.0	-12.0	136+33.0	-12.0	244.0	SOLID	244.0
PRWOND	133+90.0	12.0	146+24.0	12.0	1,234.0	SOLID	1,234.0
PRWOND	137+19.0	-12.0	139+30.0	-12.0	211.0	SOLID	211.0
PRWOND	140+23.0	-12.0	142+23.0	-12.0	200.0	SOLID	200.0
PRWOND	143+14.0	-12.0	145+21.0	-12.0	207.0	SOLID	207.0
PRWOND	122+54.0	0.0	123+33.0	0.0	79.0	DBL CL	158.0
PRWOND	124+30.0	0.0	126+60.0	0.0	230.0	DBL CL	460.0
PRWOND	144+29.0	0.0	145+21.0	0.0	92.0	DBL CL	184.0
TOTAL =					11,009.0		10,742.0

**SCHEDULE OF QUANTITIES
THOMPSON ROAD**

HOT-MIX ASPHALT SURFACE REMOVAL – BUTT JOINT

LOCATION	WIDTH (FT)	LENGTH (FT)	AREA (SF)	AREA (SY)
SOUTH OF VINE (BEGIN PROJECT)	24.0	4.50	108.0	12.0
VINE	18.0	4.50	81.0	9.0
ORIOLE	21.0	4.50	95.0	11.0
EVERGREEN	22.0	4.50	99.0	11.0
PINE	20.0	4.50	90.0	10.0
ELM	26.0	4.50	117.0	13.0
MEMORY	25.0	4.50	113.0	13.0
MEMORY	19.0	4.50	86.0	10.0
SHADY	24.0	4.50	108.0	12.0
SHADY	28.0	4.50	126.0	14.0
SUNSET	21.0	4.50	95.0	11.0
SUNSET	27.0	4.50	122.0	14.0
RAMBLE	27.0	4.50	122.0	14.0
RAMBLE	29.0	4.50	131.0	15.0
ACORN	23.0	4.50	104.0	12.0
ACORN	61.0	4.50	275.0	31.0
WOODY	26.0	4.50	117.0	13.0
CORAL	41.0	4.50	185.0	21.0
HIGHLAND	32.0	4.50	144.0	16.0
ALDEN	23.0	4.50	104.0	12.0
DORR	35.0	4.50	158.0	18.0
BURTON	32.0	4.50	144.0	16.0
BURTON	28.0	4.50	126.0	14.0
RILEY	30.0	4.50	135.0	15.0
WONDERMERE	21.0	4.50	95.0	11.0
NORTH OF WONDERMERE (END PROJECT)	22.0	4.50	99.0	11.0
TOTALS =			3,180.00	360.00

THERMOPLASTIC PAVEMENT MARKING – LINE 4"

LOCATION	STA	OFFSET	TO STA	OFFSET	LENGTH (FT)	TYPE	NET LENGTH (FT)
PRTHOM1	301+00.0	0.0	311+16.0	0.0	1,016.0	SK DA	254.0
PRTHOM1	312+05.0	0.0	314+18.0	0.0	213.0	SOLID SKIP	267.0
PRTHOM1	315+14.0	0.0	317+42.0	0.0	228.0	SOLID SKIP	285.0
PRTHOM1	341+76.0	0.0	343+24.0	0.0	148.0	SOLID SKIP	185.0
PRTHOM1	345+15.0	0.0	347+84.0	0.0	269.0	SK DA	68.0
PRTHOM1	348+92.0	0.0	352+15.0	0.0	323.0	SK DA	81.0
PRTHOM1	353+13.0	0.0	357+98.0	0.0	485.0	SK DA	122.0
PRTHOM1	359+02.0	0.0	360+56.0	0.0	154.0	SK DA	39.0
PRTHOM1	301+00.0	-11.0	311+16.0	-11.0	1,016.0	SOLID	1,016.0
PRTHOM1	301+00.0	11.0	321+52.0	11.0	2,052.0	SOLID	2,052.0
PRTHOM1	312+05.0	-11.0	314+18.0	-11.0	213.0	SOLID	213.0
PRTHOM1	315+14.0	-11.0	317+42.0	-11.0	228.0	SOLID	228.0
PRTHOM1	318+16.0	-11.0	320+48.0	-11.0	232.0	SOLID	232.0
PRTHOM1	321+36.0	-11.0	324+45.0	-11.0	309.0	SOLID	309.0
PRTHOM1	322+44.0	11.0	324+44.0	11.0	200.0	SOLID	200.0
PRTHOM1	325+36.0	-11.0	327+67.0	-11.0	231.0	SOLID	231.0
PRTHOM1	325+36.0	11.0	327+67.0	11.0	231.0	SOLID	231.0
PRTHOM1	328+62.0	-11.0	330+76.0	-11.0	214.0	SOLID	214.0
PRTHOM1	328+63.0	11.0	330+76.0	11.0	213.0	SOLID	213.0
PRTHOM1	331+64.0	-11.0	333+93.0	-11.0	229.0	SOLID	229.0
PRTHOM1	331+64.0	11.0	333+93.0	11.0	229.0	SOLID	229.0
PRTHOM1	334+78.0	-11.0	337+02.0	-11.0	224.0	SOLID	224.0
PRTHOM1	334+78.0	11.0	337+02.0	11.0	224.0	SOLID	224.0
PRTHOM1	338+03.0	-11.0	340+49.0	-11.0	246.0	SOLID	246.0
PRTHOM1	338+03.0	11.0	340+49.0	11.0	245.0	SOLID	245.0
PRTHOM1	341+76.0	-11.0	343+24.0	-11.0	148.0	SOLID	148.0
PRTHOM1	341+76.0	11.0	344+34.0	11.0	258.0	SOLID	258.0
PRTHOM1	344+34.0	-11.0	352+15.0	-11.0	781.0	SOLID	781.0
PRTHOM1	345+15.0	11.0	347+84.0	11.0	269.0	SOLID	269.0
PRTHOM1	348+92.0	11.0	352+15.0	11.0	323.0	SOLID	323.0
PRTHOM1	353+13.0	-11.0	360+56.0	-11.0	743.0	SOLID	743.0
PRTHOM1	353+13.0	11.0	357+98.0	11.0	485.0	SOLID	485.0
PRTHOM1	359+02.0	11.0	361+99.0	11.0	297.0	SOLID	297.0
PRTHOM1	318+16.0	0.0	320+48.0	0.0	232.0	DBL CL	464.0
PRTHOM1	322+44.0	0.0	324+45.0	0.0	201.0	DBL CL	402.0
PRTHOM1	325+36.0	0.0	327+67.0	0.0	231.0	DBL CL	462.0
PRTHOM1	328+62.0	0.0	330+76.0	0.0	214.0	DBL CL	428.0
PRTHOM1	331+64.0	0.0	333+93.0	0.0	229.0	DBL CL	458.0
PRTHOM1	334+78.0	0.0	337+02.0	0.0	224.0	DBL CL	448.0
PRTHOM1	338+03.0	0.0	340+49.0	0.0	246.0	DBL CL	492.0
TOTAL =					14,253.0		14,295.0



USER NAME = JSrzo1	DESIGNED - JJS	REVISED -
PLOT SCALE = NTS	DRAWN - JJS	REVISED -
PLOT DATE = 2/6/2012	CHECKED - AC	REVISED -
	DATE - 2/6/12	REVISED -

VILLAGE OF WONDER LAKE

**EAST WONDER LAKE ROAD & THOMPSON ROAD
SCHEDULE OF QUANTITIES**

SCALE: NTS	SHEET NO. 1 OF 1 SHEETS	STA. NA TO STA. NA
------------	-------------------------	--------------------

F.A.U. RTE. 4086 4081	SECTION 11-00007-00-PP	COUNTY MCHENRY	TOTAL SHEETS 13	SHEET NO. 5
CONTRACT NO. 63695			ILLINOIS FED. AID PROJECT	