

SUMMARY OF QUANTITIES

SPECIALTY ITEMS (Δ)	SPECIAL PROVISION (*)	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	ROADWAY 80% FEDERAL 20% LOCAL 0005
		20800150	TRENCH BACKFILL	CU YD	155	155
	*	21400100	GRADING AND SHAPING DITCHES	FOOT	1,227	1,227
		28100805	STONE DUMPED RIPRAP, CLASS A3	TON	13	13
		28200200	FILTER FABRIC	SQ YD	20	20
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,790	4,790
		40600300	AGGREGATE (PRIME COAT)	TON	96	96
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160
		40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	10	10
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	6,065	6,065
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4,340	4,340
		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	47,585	47,585
		44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	1,705	1,705
		44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	70	70
		44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	190	190
		44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	290	290
		44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	290	290
		48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,177	1,177
		542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	286	286
		542C0220	PIPE CULVERTS, CLASS C, TYPE 1 15"	FOOT	339	339
		542C1060	PIPE CULVERTS, CLASS C, TYPE 2 15"	FOOT	160	160
		542C1063	PIPE CULVERTS, CLASS C, TYPE 2 18"	FOOT	139	139
		67100100	MOBILIZATION	L SUM	1	1
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
		70300100	SHORT TERM PAVEMENT MARKING	FOOT	8,950	8,950
Δ		72900200	METAL POST - TYPE B	FOOT	60.0	60.0
Δ		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	40.00	40.00
Δ		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	50,164	50,164
Δ		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	254	254
Δ		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120
Δ		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	221	221
Δ		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	560	560
		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	395	395
	*	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	77.10	77.10
	*	X5015225	PIPE CULVERT REMOVAL (SPECIAL)	FOOT	959	959
Δ	*	X7200105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	389.50	389.50
	*	XX006343	SEEDING (COMPLETE)	SQ YD	1,644	1,644
	*	XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	1,365	1,365



HRGreen.com
 Illinois Professional Design Firm
 # 194-001322

USER NAME = JStorz
 DESIGNED - JJS
 DRAWN - JJS
 CHECKED - AC
 DATE - 1/31/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

VILLAGE OF RINGWOOD

**BARNARD MILL ROAD
 SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 1 OF 1 SHEETS STA. NA TO STA. NA

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4083	11-00004-00-RS	MCHENRY	17	3
CONTRACT NO.			63696	
ILLINOIS FED. AID PROJECT				