

PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FEDERAL PARTICIPATION		NON-PARTICIPATING
				70% FED - 30% LOCAL	ROADWAY RESURFACING 0005	UTILITIES 0043
				TRAINEES 0042		
* A2006420	TREE, QUERCUS ALBA (WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	0	0	2
* X0839900	SANITARY SEWER REMOVAL 6"	FOOT	20	0	0	20
* X0840000	SANITARY SEWER REMOVAL 8"	FOOT	70	0	0	70
* X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	200	0	0	200
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	9056	9056	0	0
* X5610004	DUCTILE IRON WATER MAIN FITTINGS	POUND	6375	0	0	6375
* X5610700	WATER MAIN REMOVAL	FOOT	140	0	0	140
* X5620040	WATER SERVICE CONNECTION 2"	EACH	1	0	0	1
* X5620116	WATER SERVICE CONNECTION (SHORT)	EACH	8	0	0	8
* X5620118	WATER SERVICE CONNECTION (LONG)	EACH	7	0	0	7
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	27	27	0	0
* XX001047	VALVE VAULTS TO BE ABANDONED	EACH	6	0	0	6
* XX001490	GATE VALVES, 8"	EACH	2	0	0	2
* XX003032	GATE VALVES, 12"	EACH	4	0	0	4
* XX003516	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) -8"	EACH	2	0	0	2
XX004774	BRICK DRIVEWAY REMOVAL AND REPLACEMENT	SQ FT	39	0	0	39
* XX005107	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) -12"	EACH	2	0	0	2
XX006247	SANITARY SEWER REMOVAL	FOOT	20	0	0	20
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0	0
* Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	26	0	0	26
Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	741	741	0	0
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	400	400	0	0
Z0056602	STORM SEWER (WATER MAIN REQUIREMENTS) 4 INCH	FOOT	20	0	0	20
Z0056606	STORM SEWER (WATER MAIN REQUIREMENTS) 10 INCH	FOOT	70	0	0	70
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	60	0	0	60
* Z0056700	SANITARY SEWER 4"	FOOT	20	0	0	20
* Z0056800	SANITARY SEWER 6"	FOOT	20	0	0	20
* Z0056900	SANITARY SEWER 8"	FOOT	70	0	0	70
Z0076600	TRAINEES	hour	500	0	500	0
* XX008656	TRACE WIRE	FOOT	2866	0	0	2866
* XX008657	WATER MAIN, DUCTILE IRON PIPE, CLASS 52, 12", DIRECTIONALLY DRILLED	FOOT	1129	0	0	1129
* XX008658	WATER MAIN, DUCTILE IRON PIPE, CLASS 52, 8", DIRECTIONALLY DRILLED	FOOT	244	0	0	244

* SPECIALTY ITEMS

FILE NAME = ...:\Cad\sheet\2253.sht	USER NAME = eds	DESIGNED - JSM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE. 1236	SECTION 08-00100-00-PV	COUNTY LAKE	TOTAL SHEETS 35	SHEET NO. 5
	PLOT SCALE = 1:8000 / 1" = 80'	DRAWN - JSM	REVISED -		SCALE: N.T.S.	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	CONTRACT NO. 63697				
	PLOT DATE = 2/28/2012	CHECKED - DNM	REVISED -		FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT								
		DATE - 02/06/12	REVISED -										