FINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
	PLOTTED		
	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

ORIGINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
	PLOTTED		
	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

SUMMARY OF QUANTITIES

URBAN

0014 BRIDGE REPAIR

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	120	120
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	102	102
	44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	1035	1035
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1073	1073
	50102400	CONCRETE REMOVAL	CU YD	29.0	29.0
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	29.0	29.0
	50300260	BRIDGE DECK GROOVING	SQ YD	1057	1057
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4010	4010
	50800515	BAR SPLICERS	EACH	48	48
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	208	208
	64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	2656	2656
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
	67100100	MOBILIZATION	L SUM	1	1
	70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
	70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2	2
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	1490	1490
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13678	13678
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4514	4514
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	825	825
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	775	775
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3315	3315
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1208	1208
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	584	584
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4
*	78100300	REPLACEMENT REFLECTOR	EACH	60	60
	78200410	GUARDRAIL MARKERS, TYPE A	EACH	43	43
	78200520	BARRIER WALL MARKERS, TYPE B	EACH	28	28
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1695	1695
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4
	Z0006012	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1017	1017
	X0012142	BRIDGE DECK SCARIFICATION 2 1/4"	SQ YD	1017	1017
	Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	10	10
	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	10	10
	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2

SUMMARY OF QUANTITIES

URBAN

0014 BRIDGE REPAIR

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE

* SPECIALTY ITEM

Rev.

FILE NAME = D264H22-sht-S00.dgn
PLOT DATE = 1/23/2012
PLOT SCALE = 50.0000 ' / IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L./K.R.K.	REVISED -	
DRAWN -	K.R.K.	REVISED -	
CHECKED -	E.J.M.	REVISED -	
DATE -	DECEMBER 2011	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 251 AT N. KINNIKINNICK CREEK

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
738	(5B-1)M-1	WINNEBAGO	24	3
		CONTRACT NO. 64H22		
		ILLINOIS		