SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50						40603310
			WIDTH	SQYD	INCHES	TONS
Stage 1						
SB	252+90.00	255+91.00	4	133.8	2	15.0
SB	257+58.00	261+00.00	4	152.0	2	17.0
NB	251+75.00	255+41.00	4	162.7	2	18.2
NB	257+04.00	260+10.00	4	136.0	2	15.2
Stage 2						
SB	252+90.00	255+45.00	4	113.3	2	12.7
SB	258+28.00	261+10.00	4	125.3	2	14.0
NB	251+60.00	254+65.00	4	135.6	2	15.2
NB	257+54.00	260+10.00	4	113.8	2	12.7
						120.0

HOT-MIX ASPHALT SURFACE REMOVAL, 2"				44000157
			WIDTH	SQYD
Stage 1				
SB	252+90.00	255+91.00	4	133.8
SB	257+58.00	261+00.00	4	152.0
NB	251+75.00	255+41.00	4	162.7
NB	257+04.00	260+10.00	4	136.0
Stage 2				
SB	252+90.00	255+45.00	4	113.3
SB	258+28.00	261+10.00	4	125.3
NB	251+60.00	254+65.00	4	135.6
NB	257+54.00	260+10.00	4	113.8
				1072.5

SHOULDER RUMBLE STRIPS, 16 INCH				64200116
				FOOT
Stage 1				
SB	252+90.00	255+91.00		301
SB	257+58.00	261+00.00		342
NB	251+75.00	255+41.00		366
NB	257+04.00	260+10.00		306
Stage 2				
SB	252+90.00	256+16.00		326
SB	257+80.00	261+10.00		330
NB	251+60.00	255+15.00		355
NB	256+80.00	260+10.00		330
				2656

SHORT TERM PAVEMENT MARKING			70300100
			FOOT
SKIP-DASH	231+40.00	260+50.00	240
YELLOW	252+90.00	261+00.00	267
WHITE	252+90.00	261+10.00	271
NORTHBOUND			
SKIP-DASH	252+25.00	271+20.00	156
YELLOW	251+75.00	260+10.00	276
WHITE	251+60.00	260+10.00	281
		TOTAL	1,490

THERMOPLASTIC PAVEMENT MARKING - LINE 4"			78000200
			FOOT
SOUTHBOUND			
YELLOW	252+90.00	261+00.00	810
WHITE	252+90.00	261+10.00	820
NORTHBOUND			
YELLOW	251+75.00	260+10.00	835
WHITE	251+60.00	260+10.00	850
			3,315

THERMOPLASTIC PAVEMENT MARKING - LINE 6"			78000400
			FOOT
SOUTHBOUND			
SKIP-DASH	231+40.00	260+60.00	730
NORTHBOUND			
SKIP-DASH	252+10.00	271+20.00	478
		TOTAL	1,208

RELOCATE TEMPORARY CONCRETE BARRIER			70400200
			FOOT
STAGE 2			
254+29.93	258+31.20		400
254+53.14	258+36.15		375
			775

TEMPORARY CONCRETE BARRIER			70400100
STAGE I			FOOT
254+25.18	258+26.61		400
254+43.07	258+76.81		425
		TOTAL	825

HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"				44000156
				SQYD
SB SOUTH APPROACH				258.0
SB NORTH APPROACH				254.0
NB SOUTH APPROACH				264.0
NB NORTH APPROACH				259.0
			TOTAL	1035

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70					40603340
			SQYD	INCHES	TONS
SB SOUTH APPROACH			258.0	1.75	25.3
SB NORTH APPROACH			254.0	1.75	24.9
NB SOUTH APPROACH			264.0	1.75	25.9
NB NORTH APPROACH			259.0	1.75	25.4
		TOTAL	1035		101.5

WORK ZONE PAVEMENT MARKING REMOVAL					70301000
TEMPORARY PAVEMENT MARKING - LINE 4"			70300220		
STAGE 1			FOOT	FOOT	SQ.FT.
SOUTHBOUND			YELLOW	WHITE	
	231+40.00	239+00.00		760	250.80
	239+00.00	243+04.00		404	133.32
	239+00.00	239+59.00		59	19.47
	239+59.00	242+71.00	312		102.96
	242+96.00	243+04.00		29	9.57
	243+91.00	244+39.00		125	41.25
	244+12.00	260+50.00		1638	540.54
	252+90.00	261+00.00	810		267.30
NORTH BOUND					
	252+25.00	271+20.00		1895	625.35
	251+75.00	260+10.00	835		275.55
STAGE 2					
SOUTHBOUND					
	231+40.00	239+00.00	760		250.80
	239+00.00	239+59.00		59	19.47
	239+00.00	243+08.00		408	134.64
	239+59.00	243+08.00	349		115.17
	243+08.00	243+08.00		12	3.96
	244+17.00	260+60.00	1,643		542.19
	252+90.00	261+10.00		820	270.60
NORTH BOUND					
	252+10.00	271+20.00	1,910		630.30
	251+60.00	260+10.00		850	280.50
			6,619	7,059	
		TOTAL	13,678		4513.74

THERMOPLASTIC PAVEMENT MARKING - LINE 8"			78000500
			FOOT
SOUTHBOUND			
WHITE	240+00.00	242+92.00	292
WHITE	240+00.00	242+92.00	292
		TOTAL	584

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)				78100105
				EACH
Stage 1				
NB	255+29.00	256+94.00		2
SB	256+05.00	257+56.00		2
				4

REPLACEMENT REFLECTOR				78100300
			FOOT	EACH
SOUTHBOUND				
SKIP-DASH	231+40.00	260+60.00	2,920	36
NORTHBOUND				
SKIP-DASH	252+10.00	271+20.00	1,910	24
				60

GUARDRAIL MARKERS, TYPE A				78200410
SOUTH BOUND			25' SPACING	EACH
	252+60.00	255+84.00		13
	253+92.00	256+20.00		9
NORTH BOUND	256+78.00	259+05.00		9
	257+13.00	260+23.00		12
TOTAL				43

BARRIER WALL MARKERS, TYPE B				78200520
SOUTH BOUND			25' SPACING	EACH
	255+84.00	257+52.00		7
	256+20.00	257+86.00		7
NORTH BOUND	255+09.00	256+78.00		7
	255+47.00	257+13.00		7
TOTAL				28

PAVEMENT MARKING REMOVAL				78300100
SOUTHBOUND			LENGTH	SQ.FT
SKIP-DASH	231+40.00	260+50.00	728	363.75
YELLOW	252+90.00	261+00.00	810	267.30
WHITE	252+90.00	261+10.00	820	270.60
NORTHBOUND				
SKIP-DASH	252+25.00	271+20.00	474	236.88
YELLOW	251+75.00	260+10.00	835	275.55
WHITE	251+60.00	260+10.00	850	280.50
TOTAL				1695

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL				78300200
Stage 1				EACH
NB	255+29.00	256+94.00		2
SB	256+05.00	257+56.00		2
		Total on Bridge		4

IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3					Z0030350
STAGE II					EACH
254+29.93					1
258+36.15					1
TOTAL					2

IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3					Z0030250
STAGE I					EACH
254+25.18					1
258+76.81					1
TOTAL					2

FINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
	PLOTTED		
	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

ORIGINAL SURVEY		BY	DATE
NOTE BOOK	SURVEYED		
	PLOTTED		
	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

FILE NAME =D264H22-sht-schedule.dgn
PLOT DATE =1/24/2012
PLOT SCALE=50.0000 ' / IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L./K.R.K.	REVISED -	
DRAWN -	K.R.K.	REVISED -	
CHECKED -	E.J.M.	REVISED -	
DATE -	DECEMBER 2011	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES - IL 251 AT N. KINNIKINNICK CREEK

SCALE: NONE | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
738	(5B-1)M-1	WINNEBAGO	24	4
		CONTRACT NO. 64H22		
		ILLINOIS		