

DATE	
BY	
SURVEYED	
FOR THE	
PROJECT	
NO. _____	
NOTE BOOK	
NO. _____	
AREAS CHECKED	

DATE	
BY	
SURVEYED	
FOR THE	
PROJECT	
NO. _____	
NOTE BOOK	
NO. _____	
AREAS CHECKED	

SUMMARY OF QUANTITIES			URBAN	0014 BRIDGE REPAIR
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	STATE
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	96	96
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	77	77
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	784	784
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	852	852
50102400	CONCRETE REMOVAL	CU YD	12.4	12.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.2	12.2
50300260	BRIDGE DECK GROOVING	SQ YD	592	592
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	880	880
50800515	BAR SPLICERS	EACH	24	24
52000110	PREFORMED JOINT STRIP SEAL	FOOT	146	146
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	2,112	2,112
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2	2
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,383	1,383
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12,138	12,138
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,046	4,046
70400100	TEMPORARY CONCRETE BARRIER	FOOT	650	650
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	600	600
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,520	2,520
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,091	1,091
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	581	581
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2
* 78100300	REPLACEMENT REFLECTOR	EACH	53	53
78200410	GUARDRAIL MARKERS, TYPE A	EACH	23	23
78200520	BARRIER WALL MARKERS, TYPE B	EACH	12	12
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,766	1,766
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2
Z0006014	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	637	637
Z0012144	BRIDGE DECK SCARIFICATION 2 1/2"	SQ YD	637	637
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	10	10
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	10	10

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN	0014 BRIDGE REPAIR
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	STATE
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2

FILE NAME = D264H23-sht-500.dgn  
 PLOT DATE = 1/23/2012  
 PLOT SCALE = 50.0000' / IN.



**CHRISTIAN-ROCHE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED	- G.F.L./K.R.K.	REVISED	-
DRAWN	- K.R.K.	REVISED	-
CHECKED	- E.J.M.	REVISED	-
DATE	- DECEMBER 2011	REVISED	-

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**  
**IL 251 AT S. KINNICKINICK CREEK**  
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
738	(5B-2)M	WINNEBAGO	22	3
			CONTRACT NO. 64H23	

Rev.