

PAVEMENT MARKING SCHEDULE														
LOCATION		70300220	70301000	78005110	78005130	78005140	78100100	78100105	78100200	78300100	78300200	COLOR	NOTE	LOCATION
		TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING - LINE 4"	EPOXY PAVEMENT MARKING - LINE 6"	EPOXY PAVEMENT MARKING - LINE 8"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
BEGIN STATION	END STATION	FOOT	SQ FT	FOOT	FOOT	FOOT	EACH	EACH	EACH	SQ FT	EACH			
STAGE 1														
2361+00.00	2381+00.00	2000	667									White	Solid edge line	NB lane on RT
16+43.50	20+37.70	394	131									Yellow	Solid edge line	Baxter Rd on-ramp, LT
16+43.50	24+87.60	844	281									White	Solid edge line	Baxter Rd on-ramp, RT
2385+50.00	2444+87.00	5954	1985									White	Solid edge line	NB lane on RT thru crossover
2401+00.00	2447+00.00	4615	1538									Yellow	Solid edge line	NB lane on LT thru crossover
2405+35.00	2448+62.50	4328	1443									White	Solid edge line	SB lane on RT
2407+00.00	2473+50.00	6661	2220									Yellow	Solid edge line	SB lane on LT
2361+00.00	2371+00.00									83				NB center skip
2377+06.00	2378+23.00									78				NB gore
16+43.50	17+60.20									78				On ramp gore
2401+00.00	2404+00.00									100				NB edge LT
2443+00.00	2447+00.00									133				NB edge LT
2405+35.00	2448+62.50									1443				SB edge RT
2405+00.00	2442+00.00									1233				SB edge LT
2463+50.00	2473+50.00									83				SB center skip
2361+00.00	2371+00.00										13			NB center skip
2418+81.00	2430+69.00										15			NB bridge & approach
2463+50.00	2473+50.00										13			SB center skip
2361+00.00	2380+00.00								48					NB RT
2380+00.00	2381+00.00								3					NB RT
2385+50.00	2401+00.00								39					NB RT
16+43.50	19+37.20								7					Ent Ramp Lt
16+43.50	19+37.20								7					Ent Ramp Rt
19+37.20	20+38.00								3					Ent Ramp Lt
19+37.20	24+88.00								14					Ent Ramp Rt
2401+00.00	2409+00.00								40					NB LT
2401+00.00	2409+38.20								42					NB RT
2409+38.20	2410+00.00								2					NB RT
2405+35.00	2410+00.00								12					SB RT
2410+00.00	2416+54.40								16					NB RT
2410+00.00	2417+77.20								19					SB RT
2433+05.50	2438+61.90								14					NB RT
2433+35.20	2440+00.00								17					SB RT
2438+61.90	2440+00.00								7					NB RT
2440+00.00	2470+00.00								75					SB LT
2440+00.00	2448+62.50								22					SB RT
2440+00.00	2444+87.00								24					NB RT
SUBTOTAL		24796	8265	0	0	0	0	0	411	3231	41			