

PAVING MATERIALS

LOCATION	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SUB-BASE GRAN MATL TY A 6"	SUB-BASE GRAN MATL TY A 12"	AGG SURF CSE, TYPE B	BIT MATLS PRIME COAT	LEVELING BINDER (MACHINE METHOD), N50	HMA SURFACE REMOVAL - BUTT JOINT	HMA BINDER CSE, IL-19.0, N50	HMA SURF CSE, MIX "C", N50	BR APPR PVT CON (FLX)	PCC DRIVEWAY PVT, 6"	HMA SURFACE REMOVAL, VARIABLE DEPTH
	SQ YD	SQ YD	SQ YD	TON	GALLON	TON	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD
STA 113+90 TO STA 114+57.18												194
STA 113+90.00 TO STA 115+99.88					51				51			
STA 113+90.00 TO STA 116+05.88												
STA 113+90 LT TO STA 10+57.73 LT		32										
STA 113+90 RT TO STA 115+76.53 RT		62										
STA 113+90 TO STA 115+93.97											29	
STA 114+03.4 RT (PE)						60		128				
STA 114+20 TO STA 116+05.88					87							
STA 114+61.3 RT (PE)											29	
STA 115+17.3 RT (PE)											26	
STA 115+76.53 RT TO STA 116+05.88 RT		7										
STA 115+90.84 LT TO STA 116+05.88 LT		7										
STA 115+93.96 TO STA 116+32.43	20		40									
STA 115+93.96 TO STA 116+97.13						3		18	14			
STA 115+99.88 TO STA 116+05.88										18		
STA 116+57.49 TO STA 116+97.13	20		20									
STA 116+88.40 RT (PE)				18							28	
STA 116+90.88 TO STA 116+96.88										18		
STA 116+90.88 TO STA 117+47.00					39							
STA 116+90.88 LT TO STA 117+13.62 LT		8										
STA 116+90.88 RT TO STA 117+13.62 RT		8										
STA 116+97.13 TO STA 118+25						32						
STA 117+13.62 LT TO STA 118+25.00 LT		40										
STA 117+13.62 RT TO STA 118+25 RT		39										
STA 117+43.67 TO STA 117+95					24			56				
STA 117+43.67 TO STA 118+25.00					19				20			
STA 117+95 TO STA 118+25							87					
STA 10+13.00 TO STA 10+63.73					23	6			11			124
STA 10+57.73 LT TO STA 10+63.73 LT		3										
STA 10+57.73 RT TO STA 115+90.84 LT		51										
STA 10+63.73 RT TO STA 10+57.73 RT		3										
NW QUAD					2	2			2			16
NE QUAD					2	2			2			24
TOTAL	40	260	60	18	247	105	87	202	100	36	112	358

TEMPORARY PAVING MATERIALS

LOCATION	AGGREGATE FOR TEMPORARY ACCESS
	TON
STA 114+03.4 RT	12
STA 114+61.3 RT	12
STA 115+17.3 RT	12
STA 116+88.4 RT	12
TOTAL	48

REMOVAL OF PAVING MATERIALS

LOCATION	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL
	SQ YD	FOOT
STA 10+60 RT TO STA 116+36 RT		201
STA 113+90 LT TO STA 10+60 LT		95
STA 113+90 RT TO STA 116+36 RT		234
STA 115+93.96 TO STA 116+32.43	113	
STA 116+57.49 TO STA 116+97.13	117	
STA 116+60 LT TO STA 117+47 LT		89
STA 116+60 RT TO STA 117+47 RT		89
STA 117+43.67 LT TO STA 118+25 LT		81
STA 117+43.67 RT TO STA 118+25 RT		81
TOTAL	230	870

FILE NAME =	USER NAME = #USER#	DESIGNED - JML	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
#FILE#		DRAWN - JJO	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	623	(G-1) BR-2	LASALLE	48	8
	PLOT SCALE = #SCALE#	CHECKED - MSW	REVISED -												
	PLOT DATE = #DATE#	DATE - 11/07/11	REVISED -												