



623	0-1-1	LA SALLE	1/20	45
Revised	Revised	Revised	Revised	Revised

**BILL OF MATERIAL**

ITEM	QUANT.
Class X concrete cu. yds.	44.6
Reinforcement Bars Lbs.	7130
Structure Excavation Cu. yds.	461

**BAR LIST**

BAR NO.	SIZE	LENGTH	SHAPE
F3	#5	2'-9"	
F4	#6	9'-8"	
F5	#5	8'-6"	
H10	#6	17'-9"	
H11	#6	25'-0"	
H12	#6	9'-4"	
H13	#4	4'-0"	
H14	#4	20'-2"	
H15	#4	16'-6"	
H16	#4	17'-6"	
H17	#4	21'-9"	
N3	#6	9'-11"	J
N4	#7	7'-7"	J
N5	#5	4'-3"	J
U1	#4	5'-4"	J
V20	#5	12'-9"	
V21	#5	15'-9"	
V22	#4	14'-6"	
V23	#4	18'-2"	
V24	#4	10'-0"	
V25	#4	11'-0"	
V26	#4	4'-3"	
V27	#4	10'-3"	
V28	#4	8'-8"	
V29	#4	8'-8"	
V30	#4	4'-6"	
V31	#5	15'-0"	
V32	#5	3'-8"	
V33	#5	2'-6"	
W4	#5	22'-6"	
W5	#5	17'-3"	
W6	#5	28'-0"	
W7	#5	21'-0"	

FOR INFORMATIONAL USE ONLY

**Farnsworth GROUP, INC.**  
2709 McGraw Drive  
Bloomington, Illinois 61704  
309/663-8435, 309/663-1571 fax

DESIGNED - JML	REVISED
CHECKED - MSW	REVISED
DRAWN - DJM	REVISED
CHECKED - MSW	REVISED

DATE - 11/07/11

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**EXISTING PLANS**  
**STRUCTURE NO. 050-0184**  
SHEET NO. B20 OF 20 SHEETS

F.A.P. RTE. 623	SECTION (G-1) BR-2	COUNTY LASALLE	TOTAL SHEETS 48	SHEET NO. 36
ILLINOIS FED. AID PROJECT				CONTRACT NO. 66972