

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE ROADWAY 0005 RURAL
20200100	EARTH EXCAVATION	CU YD	247	247
20400800	FURNISHED EXCAVATION	CU YD	2062	2062
25000110	SEEDING, CLASS 1A	ACRE	1.81	1.81
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	163	163
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	163	163
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	163	163
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	8712	8712
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	1033	1033
42001200	PAVEMENT FABRIC	SQ YD	400	400
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	300	300
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	400	400
44000600	SIDEWALK REMOVAL	SQ FT	300	300
44004250	PAVED SHOULDER REMOVAL	SQ YD	879	879
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	400	400
44201299	DOWEL BARS 1 1/2"	EACH	532	532
44213200	SAW CUTS	FOOT	1368	1368
45100200	CRACK FILLING	POUND	12	12
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	250	250
60608700	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (ABUTTING EXISTING PAVEMENT)	FOOT	150	150
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	2592	2592
63500105	DELINEATORS	EACH	266	266
67100100	MOBILIZATION	L SUM	1	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	9	9
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	8464	8464
X4510100	CRACK ROUTING AND FILLING	POUND	35	35
Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	1296	1296

* SPECIALITY ITEM