

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				90% FED 10% STATE ROADWAY 0005 URBAN
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8892	8892
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	31	31
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	12370	12370
44200541	CLASS A PATCHES, TYPE II, 9 INCH	SQ YD	200	200
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	178	178
44213000	PATCHING REINFORCEMENT	SQ YD	378	378
44213200	SAW CUTS	FOOT	2166	2166
48203100	HOT-MIX ASPHALT SHOULDERS	TON	127	127
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4

△ SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\pwwork\pwwork\duncanbd\0292276\0366896-sht-500.dgn	DRAWN -	REVISED -	55					D3 INTERMITTENT RS 2012-1	LIVINGSTON	8	3	
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 66B96					
PLOT DATE = 2/9/2012	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									