

80% FED
20% STATE
URBAN

CODE NO.	SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
	ITEM				ROADWAY 0001	BRIDGE 0008	LIGHTING 0021
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"		SQ YD	1,530	1,530		
44000500	COMBINATION CURB AND GUTTER REMOVAL		FOOT	1,712	1,712		
44003100	MEDIAN REMOVAL		SQ FT	9,039	9,039		
44004250	PAVED SHOULDER REMOVAL		SQ YD	459	459		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH		SQ YD	864	864		
44201809	CLASS D PATCHES, TYPE IV, 13 INCH		SQ YD	54	54		
48101200	AGGREGATE SHOULDERS, TYPE B		TON	36	36		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"		SQ YD	459	459		
50105220	PIPE CULVERT REMOVAL		FOOT	114	114		
50200100	STRUCTURE EXCAVATION		CU YD	864		864	
50300100	FLOOR DRAINS		EACH	4		4	
50300225	CONCRETE STRUCTURES		CU YD	376.8		376.8	
50300255	CONCRETE SUPERSTRUCTURE		CU YD	1,052.3		1,052.3	
50300260	BRIDGE DECK GROOVING		SQ YD	2,392		2,392	
50300280	CONCRETE ENCASEMENT		CU YD	13.4		13.4	
50300300	PROTECTIVE COAT		SQ YD	3,269		3,269	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL		L SUM	1		1	
50500505	STUD SHEAR CONNECTORS		EACH	8,736		8,736	
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	321,800		321,800	
50800515	BAR SPLICERS		EACH	212		212	
51100100	SLOPE WALL 4 INCH		SQ YD	993		993	
51201600	FURNISHING STEEL PILES HP 12X53		FOOT	3,704		3,704	
51202305	DRIVING PILES		FOOT	3,704		3,704	

• SPECIALTY ITEM