

80% FED.
20% STATE

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY 0001	BRIDGE 0008	LIGHTING 0021
51203600	TEST PILE STEEL HP 12X53	EACH	2		2	
51500100	NAME PLATES	EACH	1		1	
52100520	ANCHOR BOLTS, 1"	EACH	48		48	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24		24	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	102	102		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	44	44		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	209		209	
60107600	PIPE UNDERDRAINS 4"	FOOT	444	444		
60224458	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 8 GRATE	EACH	1	1		
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	270	270		
60605300	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (MODIFIED)	FOOT	811	811		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	4,986	4,986		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	287.5	287.5		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	1		
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	45		

* SPECIALTY ITEM