



PLAN WEST APPROACH PAVEMENT



NORTH EDGE OF PARAPET

Location	Station	Offset	Theoretical Grade Elevations
End W. Appr. Pvmt.	512+37.77	-44.24	693.80
A	512+47.78	-44.26	693.76
B	512+57.79	-44.29	693.72
Bk. W. Abutment	512+67.44	-44.36	693.68

NORTH EDGE OF ROADWAY PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
End W. Appr. Pvmt.	512+33.44	-33.00	693.58
A	512+43.48	-33.00	693.53
B	512+53.51	-33.00	693.49
Bk. W. Abutment	512+63.17	-33.00	693.45

NORTH EDGE OF MEDIAN

Location	Station	Offset	Theoretical Grade Elevations
End W. Appr. Pvmt.	512+23.36	-7.00	693.05
A	512+33.47	-7.00	693.00
B	512+43.57	-7.00	692.96
Bk. W. Abutment	512+53.30	-7.00	692.92

PROFILE GRADE LINE

Location	Station	Offset	Theoretical Grade Elevations
End W. Appr. Pvmt.	512+20.62	0.00	692.90
A	512+30.75	0.00	692.86
B	512+40.87	0.00	692.82
Bk. W. Abutment	512+50.62	0.00	692.78

SOUTH EDGE OF MEDIAN

Location	Station	Offset	Theoretical Grade Elevations
End W. Appr. Pvmt.	512+17.87	7.00	692.76
A	512+28.02	7.00	692.72
B	512+38.16	7.00	692.68
Bk. W. Abutment	512+47.93	7.00	692.63

SOUTH EDGE OF ROADWAY PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
End W. Appr. Pvmt.	512+07.57	33.00	692.23
A	512+17.80	33.00	692.19
B	512+28.01	33.00	692.15
Bk. W. Abutment	512+37.85	33.00	692.11

SOUTH EDGE OF PARAPET

Location	Station	Offset	Theoretical Grade Elevations
End W. Appr. Pvmt.	512+03.61	42.90	692.03
A	512+13.84	42.97	691.99
B	512+24.07	43.01	691.94
Bk. W. Abutment	512+33.93	43.03	691.90

Hutchison Engineering, Inc.
Jacksonville & Shorewood, Illinois

USER NAME = tcoody	DESIGNED - CTM	REVISED -
PLOT SCALE = NONE	CHECKED - BAN	REVISED -
PLOT DATE = 8/22/2011	DRAWN - TAC	REVISED -
	CHECKED - CTM/BAN	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TOP OF WEST APPROACH SLAB ELEVATIONS
STRUCTURE NO. 055-0063

F.A.P. RTE. 315	SECTION 55-3HB	COUNTY McDonough	TOTAL SHEETS 103	SHEET NO. 39
CONTRACT NO. 68A40				
ILLINOIS FED. AID PROJECT				