

CONCRETE SUPERSTRUCTURE	
LOCATION	CU YD
SN 090-0101	2.2 CU.YD.
TOTAL	2.2 CU.YD.

FURNISHING AND ERECTING STRUCTURAL STEEL	
LOCATION	POUND
SN 090-0101	1710 POUND
TOTAL	1710 POUND

REINFORCEMENT BARS,EPOXY COATED	
LOCATION	POUND
SN 090-0101	360 POUND
TOTAL	360 POUND

BAR SPLICERS	
LOCATION	EACH
SN 090-0101	10 EACH
TOTAL	10 EACH

ELASTOMERIC BEARING ASSEMBLY,TYPE 1	
LOCATION	EACH
SN 090-0101	10 EACH
TOTAL	10 EACH

WATERPROOFING MEMBRANE SYSTEM	
LOCATION	SQ YD
SN 090-0101	601 SQ.YD.
TOTAL	601 SQ.YD.

TRAFFIC CONTROL AND PROTECTION,STANDARD 701201	
LOCATION	L.SUM
SN 090-0101	1 L.SUM
TOTAL	1 L.SUM

JACK AND REMOVE EXISTING BEARINGS	
LOCATION	EACH
SN 090-0101	10 EACH
TOTAL	10 EACH

TEMPORARY RAMP	
LOCATION	SQ YD
SN 090-0101	38 SQ.YD.
TOTAL	38 SQ.YD.

HOT-MIX ASPHALT SURFACE COURSE,MIX "D",N50	
LOCATION	TON
SN 090-0101 DECK	33 TON
SN 090-0101 APPROACHS	10 TON
TOTAL	43 TON

HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	
LOCATION	SQ YD
SN 090-0101	597 SQ.YD.
TOTAL	597 SQ.YD.

CONCRETE REMOVAL	
LOCATION	CU YD
SN 090-0101	2.5 CU.YD.
TOTAL	2.5 CU.YD.

PREFORMED JOINT STRIP SEAL	
LOCATION	FOOT
SN 090-0101	61 FOOT
TOTAL	61 FOOT

ANCHOR BOLTS, 1"	
LOCATION	EACH
SN 090-0101	20 EACH
TOTAL	20 EACH

TRAFFIC CONTROL AND PROTECTION,STANDARD B.L.R. 21	
LOCATION	L.SUM
SN 090-0101	1 L.SUM
TOTAL	1 L.SUM

CHANGEABLE MESSAGE SIGN	
LOCATION	CAL MO
SN 090-0101	1 CAL MO
TOTAL	1 CAL MO

HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	
LOCATION	SQ YD
SN 090-0101	116 SQ.YD.
TOTAL	116 SQ.YD.

BITUMINOUS MATERIALS (PRIME COAT)	
LOCATION	GAL
SN 090-0101	14 GAL
TOTAL	14 GAL

MOBILIZATION	
LOCATION	L.SUM
SN 090-0101	1 L.SUM
TOTAL	1 L.SUM

EPOXY PAVEMENT MARKING - LINE 4"	
LOCATION	FOOT
SN 090-0101	507 FOOT
TOTAL	507 FOOT

PAVEMENT MARKING REMOVAL	
LOCATION	SQ.FT.
SN 090-0101	3013 SQ.FT.
TOTAL	3013 SQ.FT.

SHORT - TERM PAVEMENT MARKING		
LOCATION	3 APPLICATIONS	FOOT
SN 090-0101	3 APPLICATIONS	46 FOOT
TOTAL		46 FOOT

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ.FT.
SN 090-0101	8 SQ.FT.
TOTAL	8 SQ.FT.

FILE NAME = SN.090-0101.dgn

USER NAME = appenzellerjj

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 155	SECTION 108-HB-111-2	COUNTY TAZEWELL	TOTAL SHEETS 14	SHEET NO. 9
CONTRACT NO. 68A59				
ILLINOIS FED. AID PROJECT				