

SCHEDULE OF QUANTITIES VERMILION COUNTY

MAP LOCATION	ROUTE	LOCATION	STARTING LOCATION	ENDING LOCATION	ESTIMATED AREA	AMOUNT MILESTONE VM	AMOUNT ESCORT XP	
1	I-74	EB EOP TO FENCE	LYNCH RD IN DANVILLE	2.2 MILES WEST OF LYNCH RD	15.0 ACRES	0.82 GALLON	0.94 POUNDS	URBAN
1	I-74	WB EOP TO FENCE	LYNCH RD IN DANVILLE	2.2 MILES WEST OF LYNCH RD	15.0 ACRES	0.82 GALLON	0.94 POUNDS	URBAN
2	I-74	TILTON INTERCHANGE	RR ON E END	NORTH L ST ON W END	3.0 ACRES	0.16 GALLON	0.19 POUNDS	URBAN
3	I-74	EB EOP TO FENCE	NORTH L ST IN TILTON	1.3 MILES WEST OF L ST IN TILTON	9.0 ACRES	0.49 GALLON	0.56 POUNDS	RURAL
3	I-74	WB EOP TO FENCE	NORTH L ST IN TILTON	1.3 MILES WEST OF L ST IN TILTON	9.0 ACRES	0.49 GALLON	0.56 POUNDS	RURAL
4	I-74	EB EOP TO FENCE	MELVIN R. HOLDEN	MLK INTERCHANGE	3.0 ACRES	0.16 GALLON	0.19 POUNDS	URBAN
			MAUCK LN BRIDGE					
4	I-74	WB EOP TO FENCE	MELVIN R. HOLDEN	MLK INTERCHANGE	3.0 ACRES	0.16 GALLON	0.19 POUNDS	URBAN
			MAUCK LN BRIDGE					
5	I-74	EXTERIOR RAMPS	MLK INTERCHANGE	WB OFF RAMP	2.0 ACRES	0.11 GALLON	0.13 POUNDS	URBAN
5	I-74	EXTERIOR RAMPS	MLK INTERCHANGE	WB ON RAMP	2.0 ACRES	0.11 GALLON	0.13 POUNDS	URBAN
5	I-74	EXTERIOR RAMPS	MLK INTERCHANGE	EB OFF RAMP	2.0 ACRES	0.11 GALLON	0.13 POUNDS	URBAN
5	I-74	EXTERIOR RAMPS	MLK INTERCHANGE	EB ON RAMP	2.0 ACRES	0.11 GALLON	0.13 POUNDS	URBAN
5	I-74	NE INFIELD	MLK INTERCHANGE		2.0 ACRES	0.11 GALLON	0.13 POUNDS	URBAN
5	I-74	SE INFIELD	MLK INTERCHANGE		2.0 ACRES	0.11 GALLON	0.13 POUNDS	URBAN
5	I-74	NW INFIELD	MLK INTERCHANGE		2.0 ACRES	0.11 GALLON	0.13 POUNDS	URBAN
6	I-74	WB EOP TO FENCE	MLK INTERCHANGE	0.7 MILES WEST OF MLK INT.	5.0 ACRES	0.27 GALLON	0.31 POUNDS	URBAN
6	I-74	EB EOP TO FENCE	MLK INTERCHANGE	0.7 MILES WEST OF MLK INT.	5.0 ACRES	0.27 GALLON	0.31 POUNDS	URBAN
7	I-74	WB EOP TO FENCE	MM 208	FITHIAN INTERCHANGE	63.0 ACRES	3.45 GALLON	3.94 POUNDS	RURAL
7	I-74	EB EOP TO FENCE	MM 208	FITHIAN INTERCHANGE	63.0 ACRES	3.45 GALLON	3.94 POUNDS	RURAL
8	I-74	EXTERIOR RAMPS	FITHIAN INTERCHANGE	WB OFF RAMP	2.0 ACRES	0.11 GALLON	0.13 POUNDS	RURAL
8	I-74	EXTERIOR RAMPS	FITHIAN INTERCHANGE	WB ON RAMP	2.0 ACRES	0.11 GALLON	0.13 POUNDS	RURAL
8	I-74	EXTERIOR RAMPS	FITHIAN INTERCHANGE	EB OFF RAMP	2.0 ACRES	0.11 GALLON	0.13 POUNDS	RURAL
8	I-74	EXTERIOR RAMPS	FITHIAN INTERCHANGE	EB ON RAMP	2.0 ACRES	0.11 GALLON	0.13 POUNDS	RURAL
9	I-74	WB EOP TO FENCE	FITHIAN INTERCHANGE	CHAMPAIGN CO LINE	3.0 ACRES	0.16 GALLON	0.19 POUNDS	RURAL
9	I-74	EB EOP TO FENCE	FITHIAN INTERCHANGE	CHAMPAIGN CO LINE	3.0 ACRES	0.16 GALLON	0.19 POUNDS	RURAL

ESTIMATED QUANTITIES =	221.0 ACRES	12.07 GALLON	13.88 POUNDS
ACTUAL QUANTITIES =	186.0 ACRES	10.10 GALLON	11.60 POUNDS

APPLICATION RATES:

AMINOPYRALID: 7 OUNCES (LIQUID) / ACRE
METSULFURON METHYL: 1 OUNCE (DRY) / ACRE

NOTES:

QUANTITIES LISTED IN THE ABOVE SCHEDULE EXCEEDS CONTRACT QUANTITIES. AREAS ARE ESTIMATED AND IT IS KNOWN THAT NOT ALL AREAS WILL BE ACCESSABLE AT THE TIME OF APPLICATION DUE TO WET CONDITIONS OR ADJACENT FIELD CROPS. ADDITIONAL AREAS HAVE BEEN INCLUDED TO ENSURE USE OF TOTAL CONTRACT QUANTITIES.

AT LOCATION 6, THE CONTRACTOR SHALL OMIT WEED SPRAYING OPERATIONS IN PROXIMITY OF THE MIDDLE FORK RIVER.

• CHAMPAIGN, VERMILION

FILE NAME =	USER NAME = ceerlockjd	DESIGNED - GAE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES VERMILION COUNTY	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\puidot\ceerlockjd\0296516\DS70970-sht-schedule.dgn	DRAWN - BBP	REVISED -	57.74			DS WEED SPRAYING 2012-1		7	6	
PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 70970							
PLOT DATE = 2/2/2012	DATE - 01/31/12	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE: NONE	SHEET 1 OF 1 SHEETS		STA. TO STA.		