

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FEDERAL 20% STATE ROADWAY	
				0005	
				RURAL	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	66	66	
<b>20200600</b>	<b>EXCAVATING AND GRADING EXISTING SHOULDER</b>	<b>UNIT</b>	<b>7</b>	<b>7</b>	
20400800	FURNISHED EXCAVATION	CU YD	109	109	
35800100	PREPARATION OF BASE	SQ YD	129	129	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	11	11	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23	23	
40600300	AGGREGATE (PRIME COAT)	TON	117	117	
40600625	LEVELING BINDER, (MACHINE METHOD), N50	TON	2,389	2,389	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	541	541	
40600990	TEMPORARY RAMP	SQ YD	176	176	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5,135	5,135	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	104	104	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	730	730	
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	144	144	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FEDERAL 20% STATE ROADWAY	
				0005	
				RURAL	
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	155	155	
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	331	331	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	42,111	42,111	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,580	1,580	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	307	307	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	625	625	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	300	300	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5,774	5,774	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	2	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	52,073	52,073	

\*SPECIALTY ITEM

FILE NAME =	USER NAME = sparksgn	DESIGNED - JWC	REVISED -
et:\pov\work\pavidot\sparksgn\d0221152\0672	C92-shr-500.dgn	DRAWN - JWC	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED - MSD	REVISED -
	PLOT DATE = Feb-07-2012 01:37:46PM	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET 1 OF 2 SHEETS	STA.	TO STA.

F.A.P. RTE. 514	SECTION 106RS-6	COUNTY HANCOCK	TOTAL SHEETS 26	SHEET NO. 3
CONTRACT NO. 72C92				ILLINOIS FED. AID PROJECT