

HOT-MIX ASPHALT SURFACE REMOVAL

| TYP. SEC. # | LOCATION | QUANTITY | | |
|-------------|--|--------------------|--------------------|---------------|
| | | BUTT JOINT (SQ YD) | VAR. DEPTH (SQ YD) | 1.50" (SQ YD) |
| | F. A. P. 514 (IL 94) | | | |
| (1) | STA. 5+15.16 TO STA. 5+25.16 | 207.01 | | |
| (1-2) | STA. 5+25.16 TO STA. 6+18.89 | | | 729.23 |
| (2) | STA. 6+18.89 TO STA. 6+28.89 | 53.33 | | |
| | (BRIDGE OMISSION) S. N. 034-0060 STA. 6+28.89 TO STA. 8+44.89 | | | |
| (3) | STA. 8+44.89 TO STA. 8+59.89 | 43.33 | | |
| (3-5) | STA. 8+59.89 TO STA. 14+30.00 | | 1,646.98 | |
| (6-18) | STA. 14+30.00 TO STA. 213+35.00 | | 53,080 | |
| (19-21) | STA. 213+35.00 TO STA. 218+85.00 | | 2,180.00 | |
| (21) | STA. 218+85.00 TO STA. 219+00.00 | 60.00 | | |
| | TR 57A (2600 N) LT | 41.75 | | |
| | FAS 424 (2500 N.) RT | 80.50 | | |
| | TR 71 (2500 N.) LT | 55.00 | | |
| | PROJECT TOTAL | 541 | 56,907 | 730 |

TEMPORARY RAMP

| TYP. SEC. # | LOCATION | QUANTITY (SQ YD) |
|-------------|--|------------------|
| | F. A. P. 733 (IL 61/94) | |
| (1) | STA. 5+15.16 TO STA. 5+20.16 | 114.48 |
| (2) | STA. 6+23.89 TO STA. 6+28.89 | 26.67 |
| | (BRIDGE OMISSION) S. N. 034-0060 STA. 6+28.89 TO STA. 8+44.89 | |
| (3) | STA. 8+44.89 TO STA. 8+49.89 | 14.44 |
| (21) | STA. 218+95.00 TO STA. 219+00.00 | 20.00 |
| | PROJECT TOTAL | 176 |

GUARDRAIL REMOVAL

| TYP. SEC. # | LOCATION | QUANTITY (FOOT) |
|-------------|-------------------------------------|-----------------|
| | F. A. P. 514 (IL 94) | |
| (17) | STA. 136+41.00 TO STA. 137+91.00 RT | 150 |
| (17) | STA. 136+90.00 TO STA. 138+40.00 LT | 150 |
| | PROJECT TOTAL | 300 |

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

| LOCATION | QUANTITY (EACH) |
|----------------------------------|-----------------|
| F. A. P. 514 (IL 94) | |
| Limits of Improv. to SN 034-0060 | 1 |
| SN 034-0060 to 2600 N | 62 |
| 2600N to 2600N(A) | 1 |
| 2600N(A) to 2500N | 66 |
| 2500N to 2400N | 67 |
| 2400N to Limits of Improv. | 67 |
| PROJECT TOTAL | 264 |

TREE REMOVAL (OVER 15 UNITS DIAMETER)

| LOCATION | QUANTITY (UNIT) |
|----------------------------------|-----------------|
| F. A. P. 514 (IL 94) | |
| STA. 45+60.00, 34.45' LT 66' Dia | 66 |
| PROJECT TOTAL | 66 |

RAISED REFLECTIVE PAVEMENT MARKER

| TYP. SEC. # | LOCATION | QUANTITY (EACH) |
|-------------|--|-----------------|
| | F. A. P. 514 (IL 94) | |
| (1-2) | STA. 5+15.16 TO STA. 6+28.89 | 3 |
| | (BRIDGE OMISSION) S. N. 034-0060 STA. 6+28.89 TO STA. 8+44.89 | |
| (3-21) | STA. 8+44.89 TO STA. 219+00.00 | 264 |
| | PROJECT TOTAL | 267 |

BOX CULVERT TO BE CLEANED

| TYP. SEC. # | LOCATION | QUANTITY (FOOT) |
|-------------|---|-----------------|
| | F. A. P. 514 (IL 94) | |
| (20) | Over Grove Creek S. N. 034-2009 Box Culvert C. L. Sta. 216+46.01, 4 CELL 10' x10' Length=44' | 216 |
| | PROJECT TOTAL | 216 |

| | | | |
|---|----------------------|----------------|-----------|
| FILE NAME = | USER NAME = sparksgw | DESIGNED - JWC | REVISED - |
| et:\pw\work\p\idot\sparksgw\10221152\0672\c92-sh-t-schedule.dgn | | DRAWN - JWC | REVISED - |
| | | CHECKED - MSD | REVISED - |
| | | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: 50 SHEET 1 OF 6 SHEETS STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|---------|---------|--------------------|-----------|
| 514 | 106R5-6 | HANCOCK | 26 | 5 |
| ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 72C92 | |