

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (SQ FT)
(Removal of Short-Term Pavement Marking) (After Surface Course) (1,924.44)(4/12)	641.48
PROJECT TOTAL	642

FURNISHED EXCAVATION

TYP. SEC. #	LOCATION	QUANTITY (CU YD)
	F. A. P. 514 (IL 94)	
(17)	STA. 135+18.00 TO STA. 138+67.00 RT	52
(17)	STA. 136+56.00 TO STA. 139+72.00 LT	47
	ADD 10%	1.10
	PROJECT TOTAL	109

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE

TYP. SEC. #	LOCATION	8"	12"	24"
		WHITE		
		SOLID (FOOT)	SOLID (FOOT)	SOLID (FOOT)
	F. A. P. 514 (IL 94)	PAINTED	CHEVRONS	STOP BAR
	IL 94/IL 9 INTERSECTION	ISLAND		
(1)	Sta. 5+30.00, 25' LT	171.49	87.49	
(1)	Sta. 5+37.00			18
(1)	Sta. 5+48.00			12
	TOTAL	172	88	30

HOT-MIX ASPHALT SHOULDERS 6 1/2"

TYP. SEC. #	LOCATION	QUANTITY (SQ YD)	QUANTITY (UNIT)
	F. A. P. 514 (IL 94)		
(17)	STA. 135+18.00 TO STA. 135+43.00 RT	13.89	25.0
(17)	STA. 135+43.00 TO STA. 136+81.00 RT	61.33	138.0
(17)	STA. 136+56.00 TO STA. 136+81.00 LT	13.89	25.0
(17)	STA. 136+81.00 TO STA. 138+42.00	143.11	322.0
(17)	STA. 138+42.00 TO STA. 138+67.00 RT	13.89	25.0
(17)	STA. 138+42.00 TO STA. 139+47.00 LT	46.67	105.0
(17)	STA. 139+47.00 TO STA. 139+72.00 LT	13.89	25.0
	PROJECT TOTAL	307	7

EXC & GR  
EX SHLD

PAINT PAVEMENT MARKING - LINE 5"

TYP. SEC. #	LOCATION	YELLOW			WHITE
		DBL-SOLID (FOOT)	SOLID (FOOT)	SKIP-DASH (FOOT)	SOLID (FOOT)
	F. A. P. 514 (IL 94)				
(1-2)	STA. 5+15.16 TO STA. 6+28.89 (BRIDGE OMISSION) S. N. 034-0060	227.46			227.46
	STA. 6+28.89 TO STA. 8+44.89		216	216	432
(3-21)	STA. 8+44.89 TO STA. 219+00.00			5,263.78	42,110.22
(3-7)	STA. 8+44.89 TO STA. 29+50.00		2,105		
(7-8)	STA. 33+60.00 TO STA. 41+77.00		817		
(19-21)	STA. 214+43.00 TO STA. 219+00.00		457		
	SUBTOTAL	227	3,595	5,480	42,770
	PROJECT TOTAL				52,073

SHORT-TERM PAVEMENT MARKING

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
	F. A. P. 514 (IL 94)	
(1-2)	STA. 5+15.16 TO STA. 6+28.89 (BRIDGE OMISSION) S. N. 034-0060 STA. 6+28.89 TO STA. 8+44.89	10.34
(3-21)	STA. 8+44.89 TO STA. 219+00.00	1,914.10
	SUBTOTAL (After Milling)	1,924.44
	SUBTOTAL (After Binder)	1,924.44
	SUBTOTAL (After Surface)	1,924.44
	PROJECT TOTAL	5,774

FILE NAME *	USER NAME * cao.jw	DESIGNED - JWC	REVISED -
ca:\pwwork\pwwork\cao.jw\08221152\087209\sh-schedule.dgn		DRAWN - JWC	REVISED -
PLOT SCALE * 100.0000' / in.		CHECKED - MSD	REVISED -
PLOT DATE * Feb-16-2012 01:26:54PM		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: 50 SHEET 4 OF 6 SHEETS STA. TO STA.

F.A.P. RTE. 514	SECTION 106RS-6	COUNTY HANCOCK	TOTAL SHEETS 26	SHEET NO. 8
CONTRACT NO. 72C92			ILLINOIS FED. AID PROJECT	