

INCIDENTAL HMA SURFACING

ENTRANCE & SIDE ROAD SCHEDULE

TYP SEC #	DESCRIPTION	STATION	EXIST. ENTR.	FROM E. O. P. (FOOT)	WIDTH (FOOT)	THICKNESS (INCH)	PREP. OF BASE (SQ YD)	HMA / (EX. AGGR.)		HMA / (EXIST HMA)				TOTAL (TON)	Aggr. Shldr TB AREA (SQ FT)	AGG SURF CSE TB (TON)	
								ENTR & SIDE RD.		ENTR.		SIDE RD.					
								AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)				
	[F. A. P. 514 (IL 94)]																
1	LIMITS OF IMPROVEMENT	5+15.16															
1	SECTION BEGINS	5+25.16															
	BRIDGE OMISSION	C. L. OF BRIDGE															
	S. N. 034-0060	7+59.00															
6	HMA PE w/MBT (RT)	22+47.00 RT	AGG	7	37	8	38.22	308.00	15.33					15.33	144.00	2.47	
8	HMA PE (RT)	38+12.00 RT	BIT	10	25	1.875				350.00	4.08			4.08	126.00	0.91	
8	HMA MBT (no entr) (LT)	38+12.00 LT	BIT	7	20	1.875				294.00	3.43			3.43	163.71		
8	HMA PE w/MBT (LT)	40+22.00 LT	AGG	7	49	8	55.56	500.00	10.89					10.89	180.00		
9	HMA PE (LT)	45+68.00 LT	BIT	12	11	1.875				276.00	3.22			3.22	96.00	1.91	
9	HMA PE w/MBT (LT)	47+96.00 LT	BIT	7	27	1.875	8.92	487.50	4.30					4.30	114.00	0.77	
9	TR 57 (2600 N) RT	58+47.00 RT	BIT	21.5	17	1.875						693.38	6.77	6.77	171.00	0.95	
9	TR 57 A (2600 N.) LT	59+40.00 LT	BIT	9	34	1.875						375.75	4.87	4.87	147.00		
15	FAS 424 (2500 N.) RT	112+04.00 RT	BIT	9	71	1.875						724.50	11.41	11.41	258.00		
15	TR 71 (2500 N.) LT	112+04.00 LT	BIT	9	47	1.875						495.00	7.84	7.84	186.00		
16	HMA PE w/MBT (RT)	145+75.00 RT	AGG	7	26	8	25.67	231.00	11.50					11.50	111.00	1.63	
16	TR 83 (2400 N.) RT	165+70.00 RT	BIT	17.5	18	1.875						630.00	6.39	6.39	150.00	0.64	
16	TR 83 (2400 N.) LT	165+78.00 LT	BIT	24	27	1.875						1,164.00	11.55	11.55	216.00	1.00	
16	HMA PE (LT)	179+29.00 LT	BIT	9	13	1.875				198.00	2.31			2.31	84.00	0.65	
19	SECTION ENDS	218+65.00															
19	LIMITS OF IMPROVEMENT	219+00.00															
	POWELLTON RD. RT	219+29.00 RT	BIT														
	POWELLTON RD. LT	219+37.00 LT	BIT														
Total =								128.37	1,526.50	42.02	1,118.00	13.04	4,082.63	48.83	103.89	2,146.71	10.92