

RESURFACING SCHEDULE										
LOCATION			LENGTH	WIDTH	HOT-MIX ASPHALT	HOT-MIX ASPHALT	LEVELING	HMA SURF.	BIT. MAT.	AGG. PRIME
STATION TO STATION					SURF. REM. BUTT-JOINT	SURF. REM.	BINDER (MM)	COURSE MIX "C"	PRIME CT.	CT.
					PI # 40600982 (SQ YD)	PI # 44000158 (SQ YD)	PI # 40600625 (TON)	PI # 40603310 (TON)	PI # 40600200 (TON)	PI # 40600300 (TON)
FAP 566 (IL 106)										
STA. 138+30.00	TO	STA. 141+90.00	360	24		960	41	81	0.4	2
STA. 138+30.00	TO	STA. 138+45.00	15	24	40					
STA. 141+75.00	TO	STA. 141+90.00	15	24	40					
TOTAL					80	960	41	81	0.4	2

SHORT-TERM PAVEMENT MARKING					
LOCATION	LENGTH	SPACING	NUMBER OF APPLICATIONS	SHORT-TERM PAVE MARK	WORK ZONE PAVE MARK REM
STATION TO STATION	(FT)			PI # 70300100 (FT)	PI # 70301000 (SQ FT)
IL (106)					
STA. 138+30.00 TO STA. 141+90.00	360	4' / 40'	3	120	14
TOTAL				120	14

TEMPORARY RAMPS			
LOCATION	LENGTH	WIDTH	TEMP RAMPS AREA
STATION	(FT)	(FT)	PI # 40600990 (SQ YD)
MAINLINE			
STA. 138+30.00 TO STA. 138+45.00	7.5	24	20
STA. 141+60.00 TO STA. 141+90.00	7.5	24	20
TOTAL			40

UNDERDRAIN SCHEDULE		
LOCATION	PIPE UNDERDRAIN 4"	CONC. HEADWALLS FOR PIPE DRAINS
STATION	PI # 60107600 (FT)	PI # 60100060 (EACH)
IL-106		
LT STA. 136+87.00		1
RT STA. 136+61.00		1
LT STA. 136+87.00 TO STA. 143+50.00	663	
RT STA. 136+61.00 TO STA. 143+50.00	689	
TOTAL		2