

PAVEMENT MARKING SCHEDULE

LOCATION		SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	PAINT PAVEMENT MARKING - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKERS
STA TO STA	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)
7+94	0+17	310.8	25.9	61.2	3108.0			36.0	61.2			36.0	3108.0	9.7
0+17	0+00	6.8	0.6		55.3			12.0				12.0	55.3	0.2
0+00	6+08	STATION EQUATION												
6+08	9+81	144.4	12.0		1212.3			36.0				36.0	1212.3	4.5
9+81	201+28	7610.0	634.2	61.2	42609.8				61.2				42609.8	237.8
201+28	213+70	496.8	41.4		4036.5								4036.5	15.5
213+70	223+80	404.0	33.7		3282.5								3282.5	12.6
223+80	235+81	445.2	37.1		2642.3								2642.3	13.9
235+81	246+65	433.6	36.1		3523.0								3523.0	13.6
246+65	262+35	628.0	52.3		6280.0								6280.0	19.6
262+35	272+90	422.0	35.2		3428.8								3428.8	13.2
272+90	288+56	626.4	52.2		3461.5								3461.5	19.6
288+56	299+88	452.8	37.7		3679.0								3679.0	14.2
299+88	320+18	1011.2	84.3		8212.0	289.0	87.0			289.0	87.0		7815.0	25.4
320+18	331+43	498.0	41.5		3414.8	185.0	32.0	11.0		185.0	32.0	11.0	3287.3	49.1
331+43	356+66	1415.2	117.9		8247.3	185.0	31.0			185.0	31.0		8119.8	59.5
356+66	367+41	430.0	35.8		3493.8								3493.8	29.4
367+41	380+03	484.0	40.3		4101.5								4101.5	15.1
380+03	405+00	558.8	46.6		5559.3								5559.3	17.5
405+00	409+45	178.0	14.8		1446.3								1446.3	5.6
409+45	420+45	440.0	36.7		3525.0								3525.0	13.8
420+45	554+07	5344.8	445.4		29840.5								29840.5	167.0
554+07	563+39	372.8	31.1		3029.0								3029.0	11.7
563+39	563+92	21.2	1.8		119.3								119.3	0.7
563+92	568+75	193.2	16.1		1502.8								1502.8	6.0
568+75	585+81	302.4	25.2		3838.5								3838.5	9.4
585+81	594+85	361.6	30.1		2938.0								2938.0	11.3
594+85	596+44	63.6	5.3		357.8								357.8	2.0
596+44	605+54	364.0	30.3		2826.5								2826.5	11.4
605+54	639+04	1340.0	111.7		7477.5								7477.5	41.9
639+04	646+61	302.8	25.2		2460.3								2460.3	9.5
646+61	651+35	189.6	15.8		1066.5								1066.5	5.9
651+35	656+36	200.4	16.7		1628.3								1628.3	6.3
656+36	690+60	1369.6	114.1		7528.0								7528.0	42.8
ILL 121/700 N													255.0	
IL 121/MONTROSE RD													397.0	
CENTERLINE ROAD													60588.0	
TOTAL:		27422	2285	122	179931	659	150	95	122	659	150	95	240520	916

PROTECTING OR RESETTNG SURVEY MARKERS

LOCATION	DESCRIPTION	UNIT (EACH)
0+37.84	PC	1
1+36.5	NORTHWEST CORNER SEC 36 T11N, R7E	1
2+34.17	PT	1
5+92.68	PC	1
7+29.07	PT	1
215+50.00	POT	1
215+88.00	SOUTHWEST CORNER SEC 13 T10N, R7E	1
243+68.08	POT	1
294+01.90	POT	1
295+25.00	NORTHEAST CORNER SE 1/4 SEC. 26 T10N, R7E	1
308+40.90	PC	1
317+66.04	PT	1
317+72.76	PC	1
333+25.00	PT	1
340+21.58	POT	1
341+42.00	SOUTHEAST CORNER SE 1/4 SEC. 25, T10N, R7E	1
365+49.14	POT	1
393+38.00	SOUTH QUARTER CORNER SEC. 30 T10N, R8E	1
419+86.06	SOUTHEAST CORNER SEC. 30	1
446+25.00	NORTH QUARTER CORNER SEC. 32 T10N, R8E	1
525+03.00	NORTHWEST CORNER SEC. 34 T10N, R8E	1
531+32.10	POT	1
551+69.00	NORTH QUARTER CORNER SEC. 34 T10N, R8E	1
562+32.89	POT	1
577+67.00	SOUTHEAST CORNER SEC. 27	1
593+76.44	POT	1
657+31.00	NORTH QUARTER CORNER, SEC. 36 T10N, R8E.	1
TOTAL:		27

GUARDRAIL REMOVAL

(STA TO STA)	LOCATION	SIDE	LENGTH (FEET)
7+94	6+80	RT	125
160+91	165+41	RT	450
161+33	165+83	LT	450
TOTAL:			1025

GUARDRAIL SCHEDULE		STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	GUARDRAIL MARKERS, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TERMINAL MARKER DIRECT APPLIED
LOCATION	SIDE	QUANTITY (FOOT)	QUANTITY (FOOT)	QUANTITY (EACH)	QUANTITY (EACH)	QUANTITY (EACH)
*160+91 TO 165+41	RT	350.0		4	2	2
*161+33 TO 165+83	LT		350.0	4	2	2
TOTAL:		350	350	9	4	4

\* PLACE FACE OF GUARDRAIL AT THIS LOCATION 4' OFF OF THE EDGE OF PAVEMENT