

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011 80% FEDERAL 20% STATE		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	577	577		
40701901	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11"	SQ YD	1299	1299		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4	0.4		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	35	35		
40800030	AGGREGATE (PRIME COAT)	TON	1	1		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	57	57		
44000100	PAVEMENT REMOVAL	SQ YD	1972	1972		
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	4,285	4,285		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	315	315		
44000400	GUTTER REMOVAL	FOOT	1705	1705		
44004250	PAVED SHOULDER REMOVAL	SQ YD	97	97		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3,304	3,304		
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	178	178		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,799	1,799		
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1	1		
50100400	REMOVAL OF EXISTING STRUCTURES NO.2	EACH	1	1		

30

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0011 80% FEDERAL 20% STATE		
50105220	PIPE CULVERT REMOVAL	FOOT	151	151		
50200100	STRUCTURE EXCAVATION	CU YD	71.8	71.8		
50300225	CONCRETE STRUCTURES	CU YD	77.9	77.9		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	258.3	258.3		
50300260	BRIDGE DECK GROOVING	SQ YD	567	567		
50300280	CONCRETE ENCASEMENTS	CU YD	5	5		
50300300	PROTECTIVE COAT	SQ YD	690	690		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1		
50500505	STUD SHEAR CONNECTORS	EACH	1239	1239		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	70,160	70,160		
50800515	BAR SPLICERS	EACH	579	579		
50901125	STEEL RAILING (TEMPORARY)	FOOT	27	27		
51201600	FURNISHING STEEL PILES HP 12 X 53	FOOT	988	988		
51202305	DRIVING PILES	FOOT	988	988		

FILE NAME =	USER NAME = harbaughrd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	01\pwwork\pwwid\harbaughrd\08139799\0478401-shr-S00.dgn	DRAWN -	REVISED -			770	64-1BR	MADISON	137	4	
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -			SCALE: NONE		SHEET NO. 2 OF 5 SHEETS		STA. TO STA.	
	PLOT DATE = 12/22/2011	DATE -	REVISED -			FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		CONTRACT NO. 76401	