

EROSION CONTROL SCHEDULE

LOCATION	LT OR RT	OFFSET DISTANCE	EROSION CONTROL BLANKET	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 2	SEEDING, CLASS 3A*	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2
STATION TO STATION		FOOT	SQ YD	FOOT	EACH	POUND	ACRE	ACRE	POUND	POUND	POUND	ACRE
IL 157												
STA 49+28.53 TO STA 50+00.00												
STA 50+00.00 TO STA 51+00.00						5.94	0.027		2.673	2.673	2.673	0.054
STA 51+00.00 TO STA 52+00.00						8.80	0.040		3.960	3.960	3.960	0.080
STA 52+00.00 TO STA 53+00.00						9.68	0.044		4.356	4.356	4.356	0.088
STA 53+00.00 TO STA 54+00.00						14.96	0.068		6.732	6.732	6.732	0.136
STA 54+00.00 TO STA 55+00.00				51.4		32.12	0.146		14.454	14.454	14.454	0.292
STA 55+00.00 TO STA 56+00.00				98.4		45.54	0.207		20.493	20.493	20.493	0.414
STA 56+00.00 TO STA 57+00.00				84.8		14.74	0.067		6.633	6.633	6.633	0.134
STA 57+00.00 TO STA 58+00.00				153.2		30.36	0.138		13.662	13.662	13.662	0.276
STA 58+00.00 TO STA 59+00.00				101.0		18.48	0.084		8.316	8.316	8.316	0.168
STA 59+00.00 TO STA 60+00.00				55.7		7.92	0.036		3.564	3.564	3.564	0.072
STA 60+00.00 TO STA 61+00.00						9.90	0.045		4.455	4.455	4.455	0.090
STA 61+00.00 TO STA 62+00.00						6.16	0.028		2.772	2.772	2.772	0.056
STA 62+00.00 TO STA 63+00.00						11.66	0.053		5.247	5.247	5.247	0.106
STA 63+00.00 TO STA 64+00.00						19.14	0.087		8.613	8.613	8.613	0.174
STA 64+00.00 TO STA 65+00.00						18.04	0.082		8.118	8.118	8.118	0.164
STA 65+00.00 TO STA 66+00.00						7.70	0.035		3.465	3.465	3.465	0.070
STA 66+00.00 TO STA 67+00.00						7.26	0.033		3.267	3.267	3.267	0.066
STA 67+00.00 TO STA 68+00.00						12.10	0.055		5.445	5.445	5.445	0.110
STA 68+00.00 TO STA 68+30.58						4.84	0.022		2.178	2.178	2.178	0.044
STA 57+21.79	RT	156.8			1							
OLD CARPENTER ROAD												
STA 0+00.00 TO STA 1+00.00				52.3		46.86	0.173	0.040	21.087	21.087	21.087	0.426
STA 1+00.00 TO STA 2+00.00				108.2		94.38	0.173	0.256	42.471	42.471	42.471	0.858
STA 2+00.00 TO STA 3+00.00				113.4		69.96	0.114	0.204	31.482	31.482	31.482	0.636
STA 3+00.00 TO STA 4+00.00				107.1		15.18	0.069		6.831	6.831	6.831	0.138
STA 4+00.00 TO STA 5+00.00				120.5		16.72	0.076		7.524	7.524	7.524	0.152
STA 5+00.00 TO STA 5+31.22				60.2		9.90	0.045		4.455	4.455	4.455	0.090
STA 0+56.46	LT	44.8			1							
STA 0+56.42	RT	38.9			1							
STA 4+08.48	RT	28.9			1							
SERVICE DRIVE												
STA 10+00.00 TO STA 11+00.00				75.6		24.20	0.110		10.890	10.890	10.890	0.220
STA 11+00.00 TO STA 12+00.00				153.0		28.38	0.129		12.771	12.771	12.771	0.258
STA 12+00.00 TO STA 13+00.00				75.1		27.94	0.127		12.573	12.573	12.573	0.254
STA 13+00.00 TO STA 14+00.00				100.1		28.16	0.128		12.672	12.672	12.672	0.256
STA 14+00.00 TO STA 14+79.39				69.0		12.98	0.059		5.841	5.841	5.841	0.118
CHANNEL												
STA 0+23.55 TO STA 0+53.45	LT		44.3									
STA 1+09.95 TO STA 1+28.26	RT		32.7									
TOTAL			77	1579	4	660	2.5	0.5	297	297	297	6

* SEEDING, CLASS 3A TO BE PLACED ON HILL, RIGHT SIDE OF OLD CARPENTER ROAD

RIGHT-OF-WAY MARKERS SCHEDULE

LOCATION	LT OR RT	OFFSET DISTANCE	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	RIGHT OF WAY AND PROPERTY CORNERS
STATION		FOOT	EACH	EACH
OLD CARPENTER RD. = IL ROUTE 157	RT	131.38	1	
STA. 0+26.53 = 59+48.65	= LT	= 37.88		
OLD CARPENTER RD.	RT	75.00	1	
STA. 0+48.61	RT	75.00	1	
OLD CARPENTER RD.	RT	75.00	1	
STA. 0+85.00	RT	75.00	1	
OLD CARPENTER RD. = IL ROUTE 157	LT	280.13	1	
STA. 1+09.93 = 55+26.22	= LT	= 81.13		
OLD CARPENTER RD.	LT	112.33	1	
STA. 1+21.97	LT	112.33	1	
OLD CARPENTER RD.	RT	100.00	1	
STA. 1+50.00	RT	100.00	1	
OLD CARPENTER RD.	LT	238.07	1	
STA. 1+69.49	LT	238.07	1	
OLD CARPENTER RD.	RT	105.00	1	
STA. 2+00.00	RT	105.00	1	
OLD CARPENTER RD.	LT	75.00	1	
STA. 2+41.78	LT	75.00	1	
OLD CARPENTER RD.	LT	26.19	1	
STA. 3+50.00	LT	26.19	1	
OLD CARPENTER RD.	RT	39.02	1	
STA. 3+51.70	RT	39.02	1	
OLD CARPENTER RD.	RT	40.17	1	
STA. 4+05.83	RT	40.17	1	
OLD CARPENTER RD.	RT	29.36	1	1
STA. 4+65.40	RT	29.36	1	
SERVICE DRIVE	RT	58.62	1	
STA. 10+54.49	RT	58.62	1	
SERVICE DRIVE	RT	59.21	1	
STA. 10+68.69	RT	59.21	1	
SERVICE DRIVE	RT	59.09	1	1
STA. 11+12.90	RT	59.09	1	
SERVICE DRIVE	RT	43.89	1	
STA. 11+59.21	RT	43.89	1	
SERVICE DRIVE ON IL 157 STATIONING	RT	174.51	1	1
STA. 57+87.58	RT	174.51	1	
TOTAL			17	3

SIGNING SCHEDULE

STATION	SIDE RT/LT	REMOVE SIGN PANEL - TYPE 1 SQ FT	SIGN PANEL - TYPE 1 SQ FT	WOOD SIGN SUPPORT FOOT	SIGN NUMBER	COMMENT
53+37	RT		5.7	17.5	W14-3	NO PASSING SIGN
54+22	RT	5.7				NO PASSING SIGN
54+32	RT		9	17.5	R1-1	STOP SIGN
57+25	LT	9				STOP SIGN
57+81	LT		9	16.5	R1-1	STOP SIGN
TOTAL		14.7	23.7	51.5		