

PAVEMENT MARKING SCHEDULE

LOCATION	PAVEMENT MARKING REMOVAL			SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING -4"			WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING -4"			POLYUREA PAVEMENT MARKING -4"			THERMOPLASTIC PAVEMENT MARKING - 12"	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
	YELLOW	WHITE			YELLOW	WHITE			YELLOW	WHITE		YELLOW	WHITE					
	SKIP-DASH	SOLID	SOLID		SKIP-DASH	SOLID	SOLID		SKIP-DASH	SOLID	SOLID	SKIP-DASH	SOLID	SOLID				
STATION TO STATION	SQ FT	SQ FT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
IL 157																		
STA 49+28.53 TO STA. 50+00	23.9	6.1	47.7	12.3	17.9	71.5	138.8	80.3	17.9	71.5	138.8				1	1		
STA 50+00 TO STA. 51+00	33.3	8.3	66.7	17.1	25	100	149.6	97.2	25	100	149.6				1	1		
STA 51+00 TO STA. 52+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				2	2		
STA 52+00 TO STA. 53+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				1	1		
STA 53+00 TO STA. 54+00	33.3	8.3	66.7	17.1	9.3	163	136.7	108.7	9.3	163	136.7				1	1		
STA 54+00 TO STA. 55+00	28.3	9.7	66.7	17.1	23	106.5	140.3	95.7	23	106.5	140.3				1	1		
STA 55+00 TO STA. 56+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				2	2		
STA 56+00 TO STA. 57+00	33.3	8.3	66.7	17.1	25	100	34.3	58.8	25	100	34.3	20.7	82.7	165.5	1		1	
STA 57+00 TO STA. 58+00	33.3	8.3	44	17.1	25	100	68.1	70.1	25	100	68.1	12.6	50.5	101	1		1	
STA 58+00 TO STA. 59+00	33.3	8.3	66.7	17.1	25	100	126	89.4	25	100	126				1	1		
STA 59+00 TO STA. 60+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				2	2		
STA 60+00 TO STA. 61+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				1	1		
STA 61+00 TO STA. 62+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				1	1		
STA 62+00 TO STA. 63+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				1	1		
STA 63+00 TO STA. 64+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				2	2		
STA 64+00 TO STA. 65+00	33.3	8.3	66.7	17.1	25	100	200	114	25	100	200				1	1		
STA 65+00 TO STA. 66+00	61.2	1.5	66.7	17.1	4.2	183.5	200	134.9	4.1	183.5	200				1	1		
STA 66+00 TO STA. 67+00	66.7		66.7	17.1		200	200	139		200	200				1	1		
STA 67+00 TO STA. 68+00	66.7		66.7	17.1		200	200	139		200	200				2	2		
STA 68+00 TO STA. 68+30.58	20.4		20.5	5.3		61.1	61.2	42.5		61.2	61.2							
OLD CARPENTER ROAD																		
STA 0+00.00 TO STA. 1+00				13.7		160	229.1	134.3		160	229.1			23.2				
STA 1+00 TO STA. 2+00				17.1		200	200	139		200	200							
STA 2+00 TO STA. 3+00				17.1		200	200	139		200	200							
STA 3+00 TO STA. 4+00				17.1		200	200	139		200	200							
STA 4+00 TO STA. 5+00				17.1		200	200	139		200	200							
STA 5+00 TO STA. 5+51.49				8.8		103	103	71.6		103	103							
SERVICE DRIVE																		
STA 10+00.00 TO STA. 11+00				14.0		163.2	272.5	149.8		163.2	272.5			25.8				
STA 11+00 TO STA. 12+00				17.1		200	200	139		200	200							
STA 12+00 TO STA. 13+00				17.2		200	200	139.1		200	200							
STA 13+00 TO STA. 14+00				17.2		200	200	139.1		200	200							
STA 14+00 TO STA. 14+18.30				3.2		36.6	36.6	25.5		36.6	36.6							
SUBTOTAL	733.4	133.5	1246.1		379.4	4148.4	5296.2		379.3	4148.5	5296.2	33.3	133.2	266.5				
TOTAL	2113			485	9824			3436	9824			433			49	24	22	2

TREE REMOVAL SCHEDULE

LOCATION	LT OR	OFFSET	TREE REMOVAL *	
			6 TO 15	> 15
STATION	RT	FOOT	UNIT	UNIT
55+90.11	RT	54.69		25.25
56+17.60	RT	43.31	12.5	
56+22.46	RT	43.42	8.75	
56+57.00	RT	44.19		18.75
56+57.28	RT	42.48		20
56+74.20	RT	58.86	7.5	
56+79.51	RT	66.19	7.5	
56+82.63	RT	61.71	10	
56+85.00	RT	51.47		37.5
56+86.60	RT	63.97		17.5
56+94.75	RT	60.51	7.5	
56+95.80	RT	57.41	12.5	
56+95.99	RT	55.50	7.5	
57+01.73	RT	75.98		17.5
57+06.04	RT	70.21	12.5	
57+14.90	RT	63.27		30
57+15.11	RT	73.59	8.75	
57+15.72	RT	85.77	7.5	
57+16.31	RT	78.79	12.5	
57+17.37	RT	95.43	8.75	
57+18.21	RT	82.08		17.5
57+20.29	RT	94.90	11.25	
57+31.06	RT	88.67	11.25	
57+31.24	RT	104.61	7.5	
57+34.48	RT	99.60	7.5	
57+43.80	RT	107.03		18.75
57+53.94	RT	68.50		20
57+59.53	RT	37.40	10	
57+65.02	RT	42.91		18.75
57+98.98	LT	88.23		30
58+32.23	LT	157.59		22.5
58+33.79	LT	207.23	15.25	
58+66.38	LT	131.33		20
61+34.02	LT	24.57	12.5	
63+03.38	RT	48.78	14	
TOTAL			213	314

* ESTIMATED GROWTH FROM TIME OF SURVEY (25%).