

GUARDRAIL SCHEDULE

LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
NW QUADRANT	140	62.5	1	1					1
NE QUADRANT	50	12.5	1	1					1
SW QUADRANT	41	62.5	1		1				1
SE QUADRANT	76	12.5	1		1				1
EASTBOUND						3	1	1	
WESTBOUND						3	1	1	
TOTAL	307	150	4	2	2	6	2	2	4

SURVEY MARKERS SCHEDULE

STATION	PERMANENT SURVEY MARKER TYPE I EACH	COMMENT
	IL ROUTE 157	
49+50.00	1	POT
54+22.48	1	PC
56+56.80	1	PT
63+50.00	1	POT
68+00.00	1	POT
	CARPENTER ROAD	
0+00.00	1	POT IL 157 & CARP RD.
1+63.91	1	PC
4+06.84	1	PT
5+50.00	1	POT
TOTAL	9	

TREE AND SHRUB SCHEDULE

STATION	OFFSET	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE)	SHRUB, CORYLUS AMERICANAN (AMERICANAN FILBERT)
		EACH	EACH
0+76	68	1	
1+13	61	1	
1+50	81	1	
1+77	61	1	
2+11	83	1	
2+54	61	1	
0+32	91		1
0+36	80		1
0+42	90		1
0+50	59		1
0+57	52		1
0+66	48		1
0+78	47		1
0+90	46		1
1+02	45		1
1+14	44		1
1+26	43		1
1+38	43		1
1+50	43		1
1+62	43		1
1+74	43		1
1+87	43		1
2+00	43		1
2+12	43		1
2+25	43		1
2+38	43		1
1+50	43		1
2+63	43		1
2+77	43		1
TOTALS		6	23

ALL STATIONS ARE OFF OF RELOCATED CARPENTER ROAD CENTERLINE.

STAGING SCHEDULE

LOCATION	TEMPORARY RAMP	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY PAVEMENT MARKING - LINE 6"	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TL 3	IMPACT ATTENUATOR, TEMPORARY (FULLY-REDIRECTIVE), TL 4	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TL 3	TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY RUMBLE STRIP
	SQ YD	FOOT	EACH	EACH	FOOT	FOOT	FOOT	EACH		EACH	EACH	EACH
STAGE I											1	9
STAGE II					200		200	1	1		1	
STAGE III					87.5	200	87.5	1		1		
STAGE IV											1	6
IL 157												
STA. 54+80.52 TO STA. 55+30.20				1								
STA. 55+30.20 TO STA. 56+29.55		100										
STA. 56+29.55 TO STA. 56+73.12			1									
STA. 57+00.12 TO STA. 57+43.87			1									
STA. 57+43.87 TO STA. 57+81.25		37.5										
STA. 57+81.25 TO STA. 58+31.25		50										
STA. 58+31.25 TO STA. 58+81.25				1								
TOTAL	0	187.5	2		287.5	200	287.5	2	1	1	3	15