SUMMARY OF QUANTITIES

	PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN 100% STATE I-64 ROADWAY 0005	I-55 ROADWAY 0005	I-55 RETAINING WALL 082-W310 0040	
	60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	13	6	7		
	60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	2	2	0		
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	8	8	0		
	60255500	MANHOLES TO BE ADJUSTED	EACH	7	7	0		
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	0	1		
	60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	0	1		
	60260100	INLETS TO BE ADJUSTED	EACH	6	6	0		
	60263000	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	0	1		
	60264140	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	2	2	0		
	60270050	DRAINAGE STRUCTURES, TYPE 4 WITH TWO TYPE 20 FRAME AND GRATES	EACH	5	0	5		
	60270055	DRAINAGE STRUCTURES, TYPE 5 WITH TWO TYPE 22 FRAME AND GRATES	EACH	1	0	1		
	60500040	REMOVING MANHOLES	EACH	15	4	11		
	60500050	REMOVING CATCH BASINS	EACH	9	9	0		
	60500060	REMOVING INLETS	EACH	45	13	32		
	60602500	CONCRETE GUTTER, TYPE A	FOOT	948.5	0.0	948.5		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	365.0	365.0	0.0		
	60605300	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (MODIFIED)	FOOT	4,374.5	2,442.5	1,932.0		
	60615400	PAVED DITCH, TYPE A-15	FOOT	103	10	93		
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	490	87	403		
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	4,825.0	4,162.5	662.5		
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	2	1		
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	2	2		
*	63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	13	9	4		
*	63100105	TRAFFIC BARRIER TERMINAL, TYPE 10	EACH	3	2	1		
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	15	9	6		
	63200310	GUARDRAIL REMOVAL	FOOT	5,761	4,390	1,371		
	~~63304395~~	~~TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 2~~	~~EACH~~	~~1~~	~~1~~	~~0~~		
	63500105	DELINEATORS	EACH	216	165	51		
	63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	437	426	11		

* DENOTES SPECIALTY ITEM

FILE NAME = DBTRI-76C52-sht-SOQ-05.dgn	USER NAME = searsb	DESIGNED SH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN BS	REVISED -			•	82-1-R(A), 82-1-R(B)	ST. CLAIR	629	9
	PLOT SCALE = 2.0000 ' / in.	CHECKED OP	REVISED -			• 64/998/70		CONTRACT NO. 76C52		
	PLOT DATE = 2/6/2012	DATE 1-20-12	REVISED -		SCALE: NONE / SHEET NO. 5 OF 10 SHEETS / STA. / TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		