

SUMMARY OF QUANTITIES

URBAN

PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE		
				I-64 ROADWAY	I-55 ROADWAY	I-55 RETAINING WALL 082-W310
				0005	0005	0040
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	16.5	9.0	7.5	
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	311	119	192	
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	358	0	358	
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	0	1	
72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	30	0	30	
72600100	MILE POST MARKER ASSEMBLY	EACH	18	4	14	
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1,878	1,878	0	
73000100	WOOD SIGN SUPPORT	FOOT	414.0	99.0	315.0	
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	71	0	71	
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	256	108	148	
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	224.5	66.5	158.0	
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	49.0	0.0	49.0	
73302120	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE I-C-A (30" X 4'-6")	FOOT	22	0	22	
73302160	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (30" X 5'-6")	FOOT	25.5	0.0	25.5	
73302190	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (24" X 7'-0")	FOOT	34	0	34	
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	57	57	0	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	173.90	53.30	120.60	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	6	3	3	
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1	0	1	
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	6	0	6	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	25	12	13	
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	17,176	9,174	8,002	
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	7,408	3,873	3,535	
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	1,406	347	1,059	
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	22,000	13,952	8,048	

* DENOTES SPECIALTY ITEM

FILE NAME = D8TRI-76C52-shr-S00-07.dgn

USER NAME = searab

DESIGNED SH

REVISED -

PLOT SCALE = 2.0000" / 1"

DRAWN BS

REVISED -

PLOT DATE = 2/6/2012

CHECKED OP

REVISED -

DATE 1-20-12

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 7 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
• 64/998/70	82-1-RIA), 82-1-R(B)	ST. CLAIR	629	11
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76C52	