

SUMMARY OF QUANTITIES

URBAN

PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE		
				I-64 ROADWAY	I-55 ROADWAY	I-55 RETAINING WALL 082-W310
				0005	0005	0040
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	6,895	4,082	2,813	
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	601	134	467	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,021	580	441	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	35	28	7	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	75	27	48	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	15	9	6	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,778	3,519	1,259	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	935	572	363	
80300100	LOCATING UNDERGROUND CABLE	FOOT	5,225	4,537.5	687.5	
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	200	200	0	
81603085	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2,450	2,300	150	
X0321309	CONCRETE PAD	SQ YD	63	63	0	
X0322628	FILL EXISTING PIEZOMETER	EACH	2	0	2	
X0323255	DRILLED WELL	EACH	1	0	1	
X0323265	REMOVE EXISTING RIPRAP	SQ YD	631	0	631	
X0323415	SITE CLEAN-UP	L SUM	1	0	1	
X0326694	PLUG EXISTING STORM SEWERS	CU YD	17	12	5	
X0326934	HIGH DENSITY POLYETHYLENE PIPE 12"	FOOT	114	0	114	
X0326366	ELECTRICAL EQUIPMENT REMOVAL AND SALVAGE	EACH	2	0	2	
X0327235	LOCATING UNDERGROUND UTILITIES	FOOT	100	50	50	
X0327263	COMBINED SEWERS, CLASS A, TYPE 2, 42"	FOOT	16	0	16	
X0327321	INTERSTATE WEEKEND CLOSURE, SPECIAL	EACH	2	1	1	
X0462500	SUBMERSIBLE PUMP	EACH	1	0	1	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	29,624	29,624	0	
X4404000	PARKING LOT PAVEMENT REMOVAL	SQ YD	3,513	0	3,513	

* DENOTES SPECIALTY ITEM

FILE NAME = DBTRI-76C52-shr-500-08.dgn	USER NAME = searab	DESIGNED SH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		DRAWN BS	REVISED -					82-1-RIA), 82-1-RIB)	ST. CLAIR	629	12	
	PLOT SCALE = 2.0000" = 1'	CHECKED OP	REVISED -			SCALE: NONE	SHEET NO. 8 OF 10 SHEETS	STA.	TO STA.	CONTRACT NO. 76C52		
	PLOT DATE = 2/6/2012	DATE 1-20-12	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						