

**EXISTING LEGEND:**




- (A) PCC PAVEMENT (REINFORCED)
  - (A1) - 9 1/2" AND VARIES
  - (A2) - 10" AND VARIES
  - (A3) - 10 1/4" AND VARIES
  - (A4) - 10 1/2" AND VARIES
  - (A5) - 10 3/4" AND VARIES
  - (A6) - 12" AND VARIES
- (B) PCC SHOULDERS
  - (B1) - 10 1/2" AND VARIES
  - (B2) - 12" AND VARIES
  - (B3) - 18" AND VARIES
- (C) HMA OVERLAY
  - (C1) - 2 1/4" AND VARIES
  - (C2) - 3 1/2" AND VARIES
  - (C3) - 3 3/4" AND VARIES
  - (C4) - 5 1/2" AND VARIES
  - (C5) - 6 3/4" AND VARIES
  - (C6) - 10" AND VARIES
- (D) HMA SURFACE COURSE - 6"
- (E) TEMP HMA PAVEMENT - 11 1/4"
- (F) AGGREGATE BASE COURSE, TYPE A
  - (F1) - 4" AND VARIES
  - (F2) - 4 1/2" AND VARIES
  - (F3) - 11 1/4" AND VARIES
  - (F4) - 12" AND VARIES
- (G) AGGREGATE SHOULDER, TYPE B 10 1/2"
- (H) AGGREGATE SHOULDER, TYPE B 18"
- (I) PIPE UNDERDRAIN
- (J) CONCRETE BARRIER
- (K) GUARDRAIL

**I-55 PROPOSED LEGEND:**

- (1) PORTLAND CEMENT CONCRETE PAVEMENT
  - (1A) - 10 1/2" (JOINTED) (RAMPS)
  - (1B) - 12 1/2" (JOINTED) (NB I-55)
  - (1C) - 14" (JOINTED) (NB I-55)
- (2) AGGREGATE BASE COURSE, TYPE A - 12"
- (3) CONCRETE GUTTER, TYPE A
- (4) PORTLAND CEMENT CONCRETE SHOULDERS
  - (4A) - 10"
  - (4B) - 10 1/2"
  - (4C) - 12 1/2"
  - (4D) - 14"
- (5) AGGREGATE SHLDS, TYPE B - THICKNESS SPECIFIED IN SECTION
- (6) \*6 TIE BARS, 30" LONG AT 30" C-C (IF LONGITUDINAL SAWED JOINT) / \*6 TIE BARS, 24" LONG AT 24" C-C (IF LONGITUDINAL CONSTRUCTION JOINT) (INCLUDED IN PRICE FOR BID FOR VARIOUS PCC ITEMS)
- (7) \*6 TIE BARS, 24" LONG AT 24" C-C (INCLUDED IN PRICE FOR BID FOR VARIOUS PCC ITEMS)
- (8) PIPE UNDERDRAINS - 6"
- (9) CONCRETE BARRIER SINGLE FACE, 42 INCH HEIGHT (SPECIAL)
- (10) COMB CONCRETE CURB AND GUTTER TYPE B-6.24 (MODIFIED)
- (11) SEEDING AND MULCHING (BY OTHERS)
- (12) NOT USED
- (13) POLYMERIZED HMA SC, SMA, N80 4"
- (14) POLYMERIZED HMA BC, SMA, N80 6"
- (15) STONE RIPRAP, CLASS A4
- (16) CONCRETE BARRIER DOUBLE FACE, 42 INCH HEIGHT
- (17) STEEL PLATE BEAM GUARDRAIL TYPE A, 6 FOOT POSTS BITUMINOUS MATERIALS (PRIME COAT)
- (18) CONTINUOUSLY REINFORCED PCC PAVEMENT - 12 1/2"
- (19) CONTINUOUSLY REINFORCED PCC PAVEMENT - 14"
- (20) STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"
- (21) STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"

**I-55 TYPICAL SECTION NOTES:**

- WHEN THE SUPERELEVATION RATE OF THE PAVEMENT IS BETWEEN 0% AND 4% THE SHOULDER SHALL BE SLOPED AT 4%. WHEN THE SUPERELEVATION RATE OF THE PAVEMENT EXCEEDS 4% THE SHOULDER SHALL BE SLOPED SO THAT THE ALGEBRAIC DIFFERENCE BETWEEN PAVEMENT AND SHOULDER SLOPES WILL NOT BE GREATER THAN 8%.
- WHERE THE EXISTING OVERLAY IS LESS THAN 4", CONTRACTOR SHALL ONLY MILL TO THE TOP OF EXISTING CONCRETE BELOW THE OVERLAY. THIS CONDITION MAY BE ENCOUNTERED FROM STATION 68+14 TO 73+00 (SB I-55), BUT SHOULD BE FIELD VERIFIED.
- WHERE THE EXISTING OVERLAY IS LESS THAN 4", THE CONTRACTOR SHALL OVERLAY TO THE PROPOSED ELEVATIONS SHOWN IN THE PLANS. IN ALL OTHER LOCATIONS, THE PROPOSED OVERLAY IS ESTIMATED AT 4" BUT SHALL BE BASED ON ELEVATIONS IN THE PLANS. SECTIONS WITH EXISTING NORMAL CROWNS SHOULD BE REESTABLISHED.



**HOT-MIX ASPHALT MIXTURE REQUIREMENTS**

| MIXTURE TYPE   | AC TYPE   | AIR VOIDS   |
|--|-----------|-------------|
| POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, SMA, N80 | SBS 76-22 | 4% @ 80 Gyr |
| POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, SMA, N80  | SBS 76-22 | 4% @ 80 Gyr |

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SOYD/IN