

REMOVAL SCHEDULE

SHEET	STATION	TO	STATION	TREE REMOVAL, ACRES	PAVEMENT REMOVAL	GUTTER REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	PAVED DITCH REMOVAL	CONCRETE BARRIER REMOVAL	PAVED SHOULDER REMOVAL	CONCRETE REMOVAL	GUARDRAIL REMOVAL	REMOVAL TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATOR REMOVAL	REMOVE EXISTING RIPRAP	PARKING LOT PAVEMENT REMOVAL	BRIDGE APPROACH PAVEMENT REMOVAL	FENCE REMOVAL	REMOVE AND SALVAGE IMPACT ATTENUATOR	
				ACRE	SQ YD	FOOT	FOOT	SQ FT	FOOT	FOOT	SQ YD	CU YD	FOOT	FOOT	EACH	SQ YD	SQ YD	SQ YD	FOOT	FOOT	
RAMP 55N64E																					
REM-1	BEGIN	TO	67+00.00	-	1,685	-	437	-	77	-	893	-	433	328	1	-	-	-	-	-	1
REM-2	67+50.00	TO	28+00.00 (64E)	-	1,558	279	-	-	281	-	1,014	-	563	293	1	-	-	-	-	-	-
I-64																					
REM-3	28+00.00	TO	33+50.00	-	3,189	1,120	-	-	-	915	2,750	-	148	484	1	-	-	-	-	89	-
REM-4	33+50.00	TO	39+00.00	-	3,379	803	-	-	-	1,271	3,186	2	251	-	-	-	-	-	-	-	-
REM-5	39+00.00	TO	44+50.00	-	1,411	103	-	-	-	863	2,743	-	288	-	-	-	-	-	-	-	-
REM-6	44+50.00	TO	50+00.00	-	191	-	-	-	-	389	1,142	-	86	-	-	-	-	-	-	-	-
REM-7	50+00.00	TO	55+50.00	-	-	-	-	-	-	-	-	-	1,060	-	-	-	-	-	-	-	-
REM-8	55+50.00	TO	END	-	-	-	-	-	-	-	-	-	964	-	-	-	-	-	-	-	-
64W55S																					
REM-9	115+00.00	TO	120+50.00	0.20	1,072	246	-	-	-	-	926	-	28	379	1	-	-	-	-	350	-
REM-10	120+50.00	TO	131+50.00	-	-	-	-	-	-	-	19	-	569	302	1	-	-	-	-	-	-
REM-11	131+50.00	TO	END	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
I-64 SUB-TOTALS				0.20	12,485	2,551	437	0	358	3,438	12,673	2	4,390	1,786	5	0	0	0	0	439	1
I-55																					
REM-12	64+00.00	TO	70+00.00	-	290	-	1,042	-	-	92	1,030	-	136	614	1	43	-	-	-	-	-
REM-13	70+00.00	TO	75+50.00	-	1,210	-	622	-	-	932	1,986	5	355	224	-	579	-	-	-	-	1
REM-14	75+50.00	TO	81+00.00	-	1,871	-	598	-	-	526	1,525	-	-	351	1	9	-	-	-	-	-
REM-15	81+00.00	TO	86+50.00	0.15	3,086	-	715	-	-	548	2,036	-	-	-	-	-	-	-	-	460	-
REM-16	86+50.00	TO	92+00.00	-	2,784	-	-	-	-	455	1,078	-	471	-	-	-	-	-	11	-	-
64W55N																					
REM-17	58+00.00	TO	63+00.00	0.11	630	-	-	-	-	-	513	-	409	-	-	-	-	-	-	325	-
70E55N																					
REM-18	76+00.00	TO	82+00.00	0.17	2,385	847	-	1,229	-	24	-	-	-	-	-	-	3,513	-	672	-	-
I-55 SUB-TOTALS				0.43	12,256	847	2,977	1,229	0	2,577	8,168	5	1,371	1,189	2	631	3,513	11	1,457	1	1
TOTALS				0.75	24,741	3,398	3,414	1,229	358	6,015	20,841	7	5,761	2,975	7	631	3,513	11	1,896	2	2

NOTE:
1. TREE REMOVAL, ACRES ACRES TOTAL IS ROUNDED TO THE NEAREST 0.25 ACRE.