

**FENCE ITEM SCHEDULE**

DESCRIP.	STATION	O/S	CHAIN LINK FENCE - 6'	CHAIN LINK GATES, 6' X 12' DOUBLE
			FOOT	EACH
<b>RAMP P BASELINE</b>				
BEGIN	20+21.83	62.72 RT		-
PI	21+26.06	75.64 RT	106	-
PI	21+42.53	153.50 RT	80	-
PI	23+53.21	108.94 RT	220	-
PI	23+46.34	70.82 RT	39	-
PI	24+99.08	44.54 RT	157	-
END	25+49.36	30.72 RT	53	-
BEGIN	26+43.03	49.19 RT		
PI	26+66.64	75.95 RT	37	-
PI	29+60.96	58.06 RT	302	-
PI	30+13.23	42.04 RT	56	-
END	30+38.19	15.49 RT	37	-
<b>ALLOWANCE</b>			-	2

1,087      2

NOTE :  
1. CHAIN LINK GATES TO BE USED PER IDOT AND THE ENGINEER'S PREFERENCE. CONTRACTOR SHALL COORDINATE LOCATIONS, IF ANY, WITH THE RE.

**CONCRETE CURB AND GUTTER AND MEDIAN SCHEDULE**

SHEET	STATION	TO	STATION	CONCRETE GUTTER, TYPE A	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 <sup>2</sup>	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 MODIFIED <sup>2</sup>	PAVED DITCH, TYPE A-15
				FOOT	FOOT	FOOT	FOOT
<b>RAMP 55N64E</b>							
PLAN-1	BEGIN	TO	67+00.00	-	-	439.0	-
PLAN-2	67+50.00	TO	28+00 (64E)	-	-	45.0	-
<b>I-64</b>							
PLAN-3	28+00.00	TO	33+50.00	-	-	796.0	-
PLAN-4	33+50.00	TO	39+00.00	-	-	461.0	-
PLAN-5	39+00.00	TO	44+50.00	-	-	612.5	-
PLAN-6	44+50.00	TO	50+00.00	-	-	-	-
PLAN-7	50+00.00	TO	55+50.00	-	-	-	-
PLAN-8	55+50.00	TO	END	-	365.0	-	-
<b>64W55S</b>							
PLAN-9	115+00.00	TO	120+50.00	-	-	89.0	10.0
PLAN-10	120+50.00	TO	131+50.00	-	-	-	-
PLAN-11	131+50.00	TO	END	-	-	-	-
<b>I-64 SUB-TOTALS</b>				<b>0</b>	<b>365.0</b>	<b>2442.5</b>	<b>10.0</b>

SHEET	STATION	TO	STATION	CONCRETE GUTTER, TYPE A	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 <sup>2</sup>	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 MODIFIED <sup>2</sup>	PAVED DITCH, TYPE A-15
				FOOT	FOOT	FOOT	FOOT
<b>NB I-55</b>							
PLAN-12	64+00.00	TO	70+00.00	494.0	-	307.0	-
PLAN-13	70+00.00	TO	75+50.00	86.0	-	648.0	-
PLAN-14	75+50.00	TO	81+00.00	40.5	-	596.0	-
PLAN-15	81+00.00	TO	86+50.00	242.0	-	381.0	-
PLAN-16	86+50.00	TO	92+00.00	-	-	-	-
<b>64W55N</b>							
PLAN-17	58+00.00	TO	63+00.00	86.0	-	0.0	93.0
<b>70E55N</b>							
PLAN-18	76+00.00	TO	82+00.00	-	-	0.0	0.0
<b>I-55 SUB-TOTALS</b>				<b>948.5</b>	<b>0.0</b>	<b>1932.0</b>	<b>93.0</b>

**TOTALS      948.5      365.0      4374.5      103.0**

NOTE :  
1. DEPRESSED CURB AND GUTTER THROUGH ENTRANCES SHALL BE MEASURED FOR PAYMENT AS COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24.  
2. UNLESS OTHERWISE NOTED, ALL COMBINATION CONCRETE CURB AND GUTTER, TYPE B AND CONCRETE CURB, TYPE B ARE DEPRESSED.