

EARTHWORK SCHEDULE I-55

ALIGNMENT	STATION	TO	STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	EMBANKMENT ²	EARTHWORK BALANCE WASTE (+) OR SHORTAGE ³
I-55 NB	63+50.00	TO	64+00.00	7	6	0	+6
	64+00.00	TO	64+25.00	10	8	0	+8
	64+25.00	TO	64+50.00	34	26	0	+26
	64+50.00	TO	65+00.00	104	78	1	+77
	65+00.00	TO	65+50.00	107	81	1	+80
	65+50.00	TO	66+00.00	111	84	0	+84
	66+00.00	TO	66+50.00	116	87	1	+86
	66+50.00	TO	67+00.00	114	86	3	+83
	67+00.00	TO	67+50.00	89	67	7	+60
	67+50.00	TO	68+00.00	79	60	5	+55
	68+00.00	TO	68+50.00	75	57	1	+56
	68+50.00	TO	69+00.00	51	39	2	+37
	69+00.00	TO	69+50.00	62	47	1	+46
	69+50.00	TO	70+00.00	86	65	8	+57
	70+00.00	TO	70+50.00	92	69	16	+53
	70+50.00	TO	71+00.00	113	85	9	+76
	71+00.00	TO	71+50.00	408	306	0	+306
	71+50.00	TO	72+00.00	661	496	0	+496
	72+00.00	TO	72+50.00	589	442	0	+442
	72+50.00	TO	73+00.00	389	292	1	+291
	73+00.00	TO	73+50.00	181	136	16	+120
	73+50.00	TO	74+00.00	119	90	15	+75
	74+00.00	TO	74+50.00	108	81	0	+81
	74+50.00	TO	74+69.00	38	29	0	+29
	74+69.00	TO	75+00.00	1,408	1,056	26	+1,030
	75+00.00	TO	75+50.00	2,192	1,644	58	+1,586
	75+50.00	TO	76+00.00	2,092	1,569	85	+1,484
	76+00.00	TO	76+19.00	787	591	36	+555
	76+19.00	TO	76+50.00	385	289	57	+232
	76+50.00	TO	77+00.00	450	338	96	+242
	77+00.00	TO	77+50.00	230	173	86	+87
	77+50.00	TO	78+00.00	172	129	66	+63
	78+00.00	TO	78+50.00	159	120	57	+63
	78+50.00	TO	79+00.00	151	114	49	+65
	79+00.00	TO	79+50.00	142	107	39	+68
	79+50.00	TO	80+00.00	131	99	23	+76
	80+00.00	TO	80+50.00	133	100	13	+87
	80+50.00	TO	81+00.00	1,021	766	48	+718
	81+00.00	TO	81+50.00	1,601	1,201	66	+1,135
	81+50.00	TO	82+00.00	1,090	818	45	+773
	82+00.00	TO	82+50.00	844	633	28	+605
	82+50.00	TO	82+65.00	243	183	6	+177
	82+65.00	TO	83+00.00	783	588	15	+573
	83+00.00	TO	83+50.00	1,055	792	11	+781
	83+50.00	TO	84+00.00	787	591	0	+591
	84+00.00	TO	84+50.00	484	363	16	+347
84+50.00	TO	85+00.00	399	300	16	+284	
85+00.00	TO	85+50.00	462	347	0	+347	
85+50.00	TO	86+00.00	429	322	1	+321	
86+00.00	TO	86+50.00	371	279	1	+278	

EARTHWORK SCHEDULE I-55 (CONT.)

ALIGNMENT	STATION	TO	STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	EMBANKMENT ²	EARTHWORK BALANCE WASTE (+) OR SHORTAGE ³	
								ALIGNMENT
I-55 NB	86+50.00	TO	87+00.00	400	300	0	+300	
	87+00.00	TO	87+50.00	392	294	0	+294	
	87+50.00	TO	88+00.00	381	286	0	+286	
	88+00.00	TO	88+50.00	368	276	0	+276	
	88+50.00	TO	89+00.00	335	252	1	+251	
	89+00.00	TO	89+50.00	302	227	2	+225	
	89+50.00	TO	90+00.00	266	200	1	+199	
	90+00.00	TO	90+50.00	194	146	0	+146	
	90+50.00	TO	91+00.00	99	75	0	+75	
	91+00.00	TO	91+29.14	24	18	1	+17	
	I-55 MAINLINE SUBTOTAL				24,505	18,403	1,036	+17,367
	I-55 SB	84+01.00	TO	84+50.00	23	18	0	+18
84+50.00		TO	85+00.00	53	40	0	+40	
85+00.00		TO	85+50.00	64	48	0	+48	
85+50.00		TO	86+00.00	60	45	0	+45	
86+00.00		TO	86+50.00	55	42	0	+42	
86+50.00		TO	87+00.00	52	39	0	+39	
I-55 SB SUBTOTAL				307	232	0	+232	
RAMP 70E55N	78+46.76	TO	78+50.00	110	83	0	+83	
	78+50.00	TO	79+00.00	2,561	1,921	0	+1,921	
	79+00.00	TO	79+50.00	3,164	2,373	0	+2,373	
	79+50.00	TO	80+00.00	3,114	2,336	70	+2,266	
	80+00.00	TO	80+50.00	2,877	2,158	70	+2,088	
	80+50.00	TO	81+00.00	2,726	2,045	0	+2,045	
	81+00.00	TO	81+50.00	2,594	1,946	2	+1,944	
	81+50.00	TO	82+00.00	1,854	1,391	3	+1,388	
	82+00.00	TO	82+50.00	708	531	39	+492	
	82+50.00	TO	83+00.00	250	188	60	+128	
	83+00.00	TO	83+50.00	215	162	204	-42	
	83+50.00	TO	84+00.00	352	264	185	+79	
	84+00.00	TO	84+15.00	134	101	1	+100	
	84+15.00	TO	84+50.00	247	186	1	+185	
84+50.00	TO	85+00.00	385	289	0	+289		
85+00.00	TO	85+31.62	263	198	0	+198		
RAMP 70E55N SUBTOTAL				21,554	16,172	635	+15,537	
RAMP 64W55N-A	58+00.00	TO	58+50.00	3,516	2,637	0	+2,637	
	58+50.00	TO	59+00.00	3,772	2,829	0	+2,829	
	59+00.00	TO	59+50.00	3,617	2,713	0	+2,713	
RAMP 64W55N-A SUBTOTAL				10,905	8,179	0	+8,179	

EARTHWORK SCHEDULE I-55 SUB-TOTALS

LOCATION SUMMARY	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE ¹	EMBANKMENT ²	EARTHWORK BALANCE WASTE (+) OR SHORTAGE ³
I-55 MAINLINE SUBTOTAL	24,505	18,403	1,036	+17,367
I-55 SB SUBTOTAL	307	232	0	+232
RAMP 70E55N SUBTOTAL	21,554	16,172	635	+15,537
RAMP 64W55N-A SUBTOTAL	10,905	8,179	0	+8,179
I-55 SUB-TOTAL	57,271	42,986	1,671	+41,315
ROUNDED TOTAL⁴	57,275			

NOTES:

- ESTIMATED SHRINKAGE FACTOR = 25%
- APPROXIMATE EMBANKMENT QUANTITY IS SHOWN FOR INFORMATION ONLY.
- APPROXIMATE EARTHWORK BALANCE IS SHOWN FOR INFORMATION ONLY.
- EARTH EXCAVATION TOTAL IS ROUNDED UP TO THE NEAREST 5 CU YD.

*NOT PAY ITEM